

Annexure-V

| | | | | | |
|----------|------------------------------------------------|---------|------------------------|----------|-----|
| PROJECT | COMPRESSOR STATION WORKS AT KAILARAS & CHAINSA | CLIENT | GAIL | UNIT NO. | 071 |
| UNIT | CHAINSA COMPRESSOR STATION | JOB NO. | 6988 | | |
| ITEM NO. | 071-KA-CF-101A/B/C | SERVICE | NATURAL GAS COMPRESSOR | | |

NOTES:

1 NO. OF COMPRESSORS

IN REGULAR USE

SPARE

2

1

ABOVE CONFIGURATION IS TENTATIVE ONLY, COMPRESSOR VENDOR TO CONFIRM THE FINAL CONFIGURATION.

SPARING PHILOSOPHY SHALL BE ADOPTED KEEPING MINIMUM ONE THIRD OF THE GROSS CAPACITY AS SPARE MACHINE HAVING CAPACITY IDENTICAL TO REGULAR UNIT, SUBJECT TO MINIMUM OF ONE SPARE UNIT.

2 TOTAL FLOW RATE TO COMPRESSORS. INDIVIDUAL COMPRESSOR CAPACITY SHALL DEPEND ON CONFIGURATION.

3 SUCTION PRESSURE INDICATED IS AT THE SUCTION FLANGE OF THE COMPRESSOR. TEMPORARY STRAINER SHALL BE IN SUCTION LINE DURING START UP AND THE SAME SHALL BE REPLACED BY PERMANENT STRAINER SUBSEQUENTLY. STRAINER PRESSURE DROP OF 0.1 KG/CM² HAS BEEN CONSIDERED TO ARRIVE AT THE COMPRESSOR SUCTION PRESSURE.

4 VENDOR TO PROVIDE THE MESH SIZE AND THE PRESSURE DROP ACROSS THE PERMANENT STRAINER.

5 VENDOR SHALL SUPPLY PERFORMANCE CURVES FOR ALL CASES OF OPERATION.

6 VENDOR TO ALSO INCLUDE IN THE SCOPE OF SUPPLY ALL NORMAL INSTRUMENTATION AND CONTROL FOR EFFICIENT OPERATION, SHUTDOWN AND SAFETY REQUIREMENTS AND ESSENTIAL ACCESSORIES.

7 VENDOR TO CONFIRM THE COMPRESSOR DISCHARGE TEMPERATURE.

8 APART FROM THE VENDOR'S SCOPE OF SUPPLY AS PER P&ID NO. 6988-02-41-071-1220 & 1221, VENDOR SHALL SUPPLY ADDITIONAL INSTRUMENTATION, CONTROL & SHUTDOWN LOGIC DEVICES FOR SAFE AND EFFICIENT OPERATION OF MACHINE.

9 AUTOMATIC SPILL BACKS IS CONSIDERED FOR EACH COMPRESSOR.

10 COMPRESSOR WILL START FROM CONTROL PANEL LOCATED IN MAIN CONTROL ROOM, HOWEVER, START CLEARANCE FROM FIELD WILL BE PROVIDED. MONITORING & CONTROL OF THE COMPRESSOR STATION SHALL BE PERFORMED AT TWO LEVELS, VIZ. MASTER CONTROL CENTRE (SCADA) AND UNIT CONTROL PANEL (UCP)/ COMMON FACILITY PANEL (FCP).

11 VENDOR TO INDICATE UTILITY REQUIREMENT.

12 NORMAL SEAL GAS SUPPLY SHALL BE FROM COMPRESSOR DISCHARGE, HOWEVER, PROVISION FOR START-UP/EMERGENCY SEAL GAS FROM LINE PACK OF EXISTING HBJ PIPELINE SHALL BE MADE. PROVISION FOR CHANGE OVER FROM NORMAL TO EMERGENCY SEAL GAS SUPPLY & VIS-A-VIS IS UNDER GTC VENDOR'S SCOPE. VENDOR TO PROVIDE FLOW INDICATION AND ALARM IN SEAL GAS SUPPLY LINE.

13 VENDOR TO PROVIDE NECESSARY FILTER, ELECTRIC HEATER, PRESSURE REGULATOR, CONTROL VALVES ETC. FOR SEAL GAS SYSTEM.

14 ACCESSORIES LIKE AFTERCOOLERS, INSTRUMENTATION AND CONTROL PANEL ARE IN VENDORS SCOPE OF SUPPLY.

15 PSV ON COMPRESSOR DISCHARGE SHALL BE SET AT 104.17 KG/CM²G.

16 DESIGN TEMPERATURE SPECIFIED IS FOR DOWNSTREAM OF AFTER COOLER.

| Rev. No. | Date | Purpose | Prepared By | Reviewed By | Approved By |
|----------|------------|--------------------------------------|-------------|-------------|-------------|
| 2 | 24.02.2009 | REVISED AS MARKED | MKA | AS | AS |
| 1 | 19.02.2009 | REVISED AS PER CLIENT'S/ENGG. INPUTS | MKA | HKP | HKP |
| 0 | 02.01.2009 | ISSUED FOR COMMENTS/ENGINEERING | MKA | AS | AS |

| | | | |
|----------|------------------------------------------------|----------|------------------------|
| PROJECT | COMPRESSOR STATION WORKS AT KAILARAS & CHAINSA | CLIENT | GAIL |
| UNIT | CHAINSA COMPRESSOR STATION | JOB NO. | 6988 |
| ITEM NO. | 071-KA-CF-101A/B/C | SERVICE | NATURAL GAS COMPRESSOR |
| | | UNIT NO. | 071 |

NOTES:

17 FUEL GAS SHALL BE TAKEN FROM COMPRESSOR INLET COMMON HEADER .

| GAS COMPOSITION | - | COMPONENT | MOLE% | |
|-----------------|---|---------------------------|--------------|----------------------|
| | | | (RICH GAS) | (LEAN GAS, NOTE-28) |
| | | METHANE | 92.49 | 94.07 |
| | | ETHANE | 5.64 | 4.59 |
| | | PROPANE | 1.41 | 1.07 |
| | | I-BUTANE | 0.2 | 0.18 |
| | | N-BUTANE | 0.15 | 0.00 |
| | | N-PENTANE | 0.01 | 0.00 |
| | | NITROGEN | 0.09 | 0.09 |
| | | H2S | 6 PPMW | 6 PPMW |
| | | TOTAL SULFUR | 24 PPMW | 24 PPMW |
| | | TOTAL | 100.0 | 100.00 |
| | | SUPPLY PRESSURE KG/CM2(G) | 73.6 | 74.0 |
| | | SUPPLY TEMP. DEG. C | 34.5 | 34.4 |
| | | LHV (KCAL/KG)= | 11840 | 11860 |
| | | HC DEW POINT(DEG C)= | < -46.0 | < -46.0 |
| | | AT SUCTION PRESSURE | | |

18 Cp/Cv VALUE IS ESTIMATED FOR CALCULATION PURPOSE.

19 NOTE - DELETED.

20 COMPRESSOR VENDOR TO FURNISH SETTLE OUT PRESSURE CALCULATION AND BLOW DOWN CALCULATIONS FOR REVIEW BY EIL.

21 FOR AFTER COOLER DATA SHEET, REFER DOC. NO. 6988-071-02-DS-1401

22 VENDOR TO PROVIDE MAX. RATE OF DEPRESSURISATION DURING COMPRESSOR TRIP/ESD.

23 DISCHARGE PRESSURE INDICATED IS AT THE COMPRESSOR DISCHARGE FLANGE.

24 NECESSARY PROVISION SHALL BE KEPT FOR WASTE HEAT RECOVERY FROM GT EXHAUST IN FUTURE.

25 VENDOR TO INDICATE NITROGEN REQUIREMENT FOR EACH COMPRESSOR.

26 INDICATED IS MINIMUM RATING. VENDOR TO CHECK AND CONFIRM THE SAME.

27 VENDOR TO COMPUTE DESIGN TEMPERATURE AT COMPRESSOR DISCHARGE FLANGE BASED ON THE GOVERNING CASE OF HIGHEST DISCHARGE TEMPERATURE.

28 COMPOSITION CONSIDERED AFTER C2 / C3 RECOVERY FROM EXISTING RLNG SUPPLY OF 12 MMSCMD FROM PLL.

29 START UP/ EMERGENCY SEAL GAS SUPPLY FROM EXISTING LINE PACK OF GREP PIPELINE IS CHARACTERIZED AS BELOW.

| COMPONENTS | H2O | N2 | CO2 | H2S | C1 | C2 | C3 | I-C4 | N-C4 | I-C5 | N-C5 | C6 | C7 | MOL. WT. |
|-------------------------------|----------------|------|-----|-----|-------|------|------|------|------|------|------|------|----|----------|
| RLNG-HP LEAN GAS EX LPG MOL % | NIL | 0.13 | 1.4 | NIL | 91.80 | 2.34 | 4.07 | 0.14 | 0.1 | 0 | 0 | 0.00 | 0 | 18 |
| PRESSURE | HOLD KG/CM2 G. | | | | | | | | | | | | | |
| TEMPERATURE | HOLD KG/CM2 G. | | | | | | | | | | | | | |
| | DEW POINT HOLD | | | | | | | | | | | | | |

30 DEW POINT OF NORMAL SEAL GAS SUPPLY SHALL BE AS INDICATED IN NOTE-17

31 NOTE -DELETED

| Rev. No. | Date | Purpose | Prepared By | Reviewed By | Approved By |
|----------|------------|--------------------------------------|-------------|-------------|-------------|
| 2 | 24.02.2009 | REVISED AS MARKED | MKA | AS | AS |
| 1 | 19.02.2009 | REVISED AS PER CLIENT'S/ENGG. INPUTS | MKA | HKP | HKP |
| 0 | 02.01.2009 | ISSUED FOR COMMENTS/ENGINEERING | MKA | AS | AS |



ENGINEERS INDIA LIMITED
NEW DELHI

6988 ITEM NO.

R-R proposal no. OG1331

R
E
V

CENTRIFUGAL COMPRESSOR
DATA SHEET (API 617-6TH)
SI UNITS

REVISION NO. 0 DATE 6-Apr-08
PAGE 1 OF 6 BY J. Bygrave

1 APPLICABLE TO: PROPOSAL PURCHASE AS BUILT

2 FOR EIL - GAIL PIPELINE EXPANSION PROJECT UNIT _____

3 SITE Chainsa Station SERIAL NO. _____

4 SERVICE Gas Transmission NO. REQUIRED 2

5 CONTINUOUS INTERMITTENT STAND BY DRIVER TYPE (3.1.1) Gas Turbine

6 MANUFACTURER Rolls-Royce MODEL RFBB36 DRIVER ITEM NO. _____

7 NOTE: INFORMATION TO BE COMPLETED: BY PURCHASER BY MANUFACTURER

OPERATING CONDITIONS

(ALL DATA ON PER UNIT BASIS)

OTHER CONDITIONS (3.1.2)

13 GAS HANDLED (ALSO SEE PAGE 2)

14 nm³/h (1.013 BAR & 0 °C)

15 WEIGHT FLOW, kg/min

INLET CONDITIONS

17 PRESSURE (kg/cm²g)

18 TEMPERATURE (°C)

19 RELATIVE HUMIDITY %

20 MOLECULAR WEIGHT (Mw)

21 Cp/Cv (K_{AVG})

22 COMPRESSIBILITY

23 INLET VOLUME, (m³/s)

DISCHARGE CONDITIONS

25 PRESSURE (kg/cm²g)

26 TEMPERATURE (°C)

27 Cp/Cv (K_{AVG})

28 COMPRESSIBILITY

29 FRICTION POWER (KW)

30 KW REQUIRED (ALL LOSSES INCLUDED)

31 SPEED (RPM)

32 ESTIMATED SURGE RANGE, % (AT SPEED ABOVE)

33 POLYTROPIC HEAD (kJ/kg)

34 POLYTROPIC EFFICIENCY (%)

35 CERTIFIED POINT

36 PERFORMANCE CURVE NUMBER

PROCESS CONTROL

38 METHOD SUCTION THROTTLING VARIABLE INLET SPEED VARIATION DISCHARGE COOLED BYPASS

39 FROM _____ (BAR)(kPa abs) GUIDE VANES FROM 70 % BLOWOFF FROM Discharge

40 TO _____ (BAR)(kPa abs) (3.4.2.4) TO 105 % TO _____ TO Suction

42 SIGNAL SOURCE (3.4.2.1) Suction / Discharge Pressure, Flow

43 TYPE ELECTRONIC PNEUMATIC OTHER _____

44 RANGE 4 - 20 MA _____ (BAR)(kPa abs) _____

46 ANTI-SURGE BYPASS MANUAL AUTOMATIC NONE

48 REMARKS:

49

50



ENGINEERS INDIA LIMITED
NEW DELHI

JOB NO. 6988 ITEM NO. _____
 REVISION NO. 0 DATE 6-Apr-08
 PAGE 2 OF 6 BY J. Bygrave

R
E
V

CENTRIFUGAL COMPRESSOR
DATA SHEET (API 617-6TH)
SI UNITS

| OPERATING CONDITIONS (Continued) (3.1.2) (3.1.3) | | | | | | | | | |
|---------------------------------------------------|----------------------------------------------------------------------------------------------------------------------|--------|------------------|----------|-------------------------------------------------------------------------------------------------------------------|---|---|--------------------------|--|
| GAS ANALYSIS: | | NORMAL | OTHER CONDITIONS | | | | | REMARKS: | |
| <input type="radio"/> MOL % <input type="radio"/> | | | A | B | C | D | E | | |
| | MW | | | Rich | Lean | | | (2.11.1.3) (2.11.1.8) | |
| 5 | AIR | 28.966 | | | | | | | |
| 6 | OXYGEN | 32.000 | | | | | | | |
| 7 | NITROGEN | 28.016 | | 0.09 | 0.09 | | | | |
| 8 | WATER VAPOR | 18.016 | | NIL | NIL | | | | |
| 9 | CARBON MONOXIDE | 28.010 | | | | | | | |
| 10 | CARBON DIOXIDE | 44.010 | | | | | | | |
| 11 | HYDROGEN SULFIDE | 34.076 | | 6 PPMW | 6 PPMW | | | (2.11.1.7) | |
| 12 | HYDROGEN | 2.016 | | | | | | | |
| 13 | METHANE | 16.042 | | 92.49 | 94.07 | | | | |
| 14 | ETHYLENE | 28.052 | | | | | | | |
| 15 | ETHANE | 30.068 | | 5.64 | 4.59 | | | | |
| 16 | PROPYLENE | 42.078 | | | | | | | |
| 17 | PROPANE | 44.094 | | 1.41 | 1.07 | | | | |
| 18 | I-BUTANE | 58.120 | | 0.20 | 0.18 | | | | |
| 19 | n-BUTANE | 58.120 | | 0.15 | | | | | |
| 20 | I-PENTANE | 72.146 | | | | | | | |
| 21 | n-PENTANE | 72.146 | | 0.01 | | | | | |
| 22 | HEXANE PLUS | | | | | | | | |
| 23 | TOTAL SULPHUR | | | 24 PPMW | 24 PPMW | | | | |
| 24 | | | | | | | | | |
| 25 | TOTAL | | | 99.99 | 100.00 | | | | |
| 26 | AVG. MOL. WT. | | | 17.4 | 17.07 | | | | |
| 27 | LOCATION: (2.1.9) | | | | NOISE SPECIFICATIONS: (2.1.10) | | | | |
| 28 | <input type="radio"/> INDOOR <input checked="" type="radio"/> OUTDOOR <input type="radio"/> GRADE | | | | <input type="radio"/> APPLICABLE TO MACHINE: | | | | |
| 29 | <input type="radio"/> HEATED <input checked="" type="radio"/> UNDER ROOF <input type="radio"/> MEZZANINE | | | | SEE SPECIFICATION _____ | | | | |
| 30 | <input checked="" type="radio"/> UNHEATED <input type="radio"/> PARTIAL SIDES <input type="radio"/> _____ | | | | <input type="radio"/> APPLICABLE TO NEIGHBORHOOD: | | | | |
| 31 | <input checked="" type="radio"/> ELEC. AREA CLASSIFICATION (2.1.15) _____ | | | | SEE SPECIFICATION _____ | | | | |
| 32 | <input type="radio"/> WINTERIZATION REQ'D. (2.1.9) <input checked="" type="radio"/> TROPICALIZATION REQ'D. (3.4.6.6) | | | | ACOUSTIC HOUSING: <input type="radio"/> YES <input checked="" type="radio"/> NO | | | | |
| 33 | SITE DATA: | | | | SOUND LEVEL <u>See Note</u> dB (A) @ _____ M | | | | |
| 34 | <input checked="" type="radio"/> ELEVATION <u>197.8</u> m BAROMETER _____ BAR | | | | APPLICABLE SPECIFICATIONS: | | | | |
| 35 | <input type="radio"/> RANGE OF / 0.3 | | | | API 617, CENTRIFUGAL COMPR. FOR GEN. REFINERY SERV. | | | | |
| 36 | | | DRY BULB | WET BULB | <input checked="" type="radio"/> VENDOR HAVING UNIT RESPONSIBILITY (2.9.1.7) | | | | |
| 37 | NORMAL | °C | 45 / 85%RH | _____ | <input checked="" type="radio"/> Rolls-Royce | | | | |
| 38 | MAXIMUM | °C | 45 / 84%RH | _____ | <input type="radio"/> GOVERNING SPECIFICATION (IF DIFFERENT) | | | | |
| 39 | MINIMUM | °C | 0 / 37%RH | _____ | | | | | |
| 40 | | °C | | _____ | | | | | |
| 41 | UNUSUAL CONDITIONS: <input checked="" type="radio"/> DUST <input type="radio"/> FUMES | | | | PAINTING: | | | | |
| 42 | <input checked="" type="radio"/> OTHER (2.1.9) _____ | | | | <input checked="" type="radio"/> MANUFACTURER'S STD. | | | | |
| 43 | | | | | <input type="radio"/> OTHER _____ | | | | |
| 44 | | | | | SHIPMENT: (4.4.1) | | | | |
| 45 | REMARKS: Noise level, for the compressor package in | | | | <input type="radio"/> DOMESTIC <input type="radio"/> EXPORT <input checked="" type="radio"/> EXPORT BOXING REQ'D. | | | | |
| 46 | isolation, shall not exceed 88 dba at 1 meter. | | | | <input checked="" type="radio"/> OUTDOOR STORAGE MORE THAN 6 MONTHS (4.4.1) | | | | |
| 47 | | | | | SPARE ROTOR ASSEMBLY PACKAGED FOR (4.4.3.10) | | | | |
| 48 | | | | | <input type="radio"/> HORIZONTAL STORAGE <input type="radio"/> VERTICAL STORAGE | | | | |
| 49 | | | | | | | | | |
| 50 | | | | | | | | | |



ENGINEERS INDIA LIMITED
NEW DELHI

R
E
V

CENTRIFUGAL COMPRESSOR
DATA SHEET (API 617-6TH)
SI UNITS

JOB NO. 6988 ITEM NO. _____
REVISION NO. 0 DATE 6-Apr-08
PAGE 3 OF 6 BY J. Bygrave

CONSTRUCTION FEATURES

1
2 **SPEEDS:**
3 MAX. CONT. 5093 RPM TRIP 5350 RPM
4 MAX. TIP SPEEDS: 194.7 m/s @ 100% SPEED
5 204.4 m/s @ MAX. CONT. SPEED
6 **LATERAL CRITICAL SPEEDS (DAMPED)**
7 FIRST CRITICAL 2800 RPM 1st Brg MODE
8 SECOND CRITICAL ~7100 RPM 2nd Brg MODE
9 THIRD CRITICAL ~10600 RPM 1st Bendg MODE
10 FOURTH CRITICAL _____ RPM _____ MODE
11 LATERAL ANALYSIS REQUIRED (2.9.2.3)
12 TRAIN TORSIONAL ANALYSIS REQUIRED
13 (TURBINE DRIVEN TRAIN) (2.9.4.5)
14 **TORSIONAL CRITICAL SPEEDS:**
15 FIRST CRITICAL Per API 617 RPM
16 SECOND CRITICAL Per API 617 RPM
17 THIRD CRITICAL Per API 617 RPM
18 FOURTH CRITICAL Per API 617 RPM
19 **VIBRATION:** Std test limit 39.0 µm, RR to attempt
20 ALLOWABLE TEST LEVEL 25 µm with reasonable effort to
21 (PEAK TO PEAK) obtain
22 **ROTATION, VIEWED FROM DRIVEN END** CW CCW
23 **MATERIALS INSPECTION REQUIREMENTS (4.2.2)**
24 SPECIAL CHARPY TESTING (2.11.3)
25 RADIOGRAPHY REQUIRED FOR _____ per specification
26 ULTRASONIC REQUIRED FOR _____ plus R-R clarifications
27 MAGNETIC PARTICLE REQUIRED FOR _____ Shaft, Impellers
28 LIQUID PENETRANT REQUIRED FOR _____ Guide vanes
29 **CASING:**
30 MODEL RFBB36
31 CASING SPLIT Vertical
32 MATERIAL CASE & COVER A-34 or A-55 CAST STEEL
33 THICKNESS (mm) 76 CORR. ALLOW. (mm) 3.2
34 MAX. WORKING PRESS 150 (BARG)
35 MAX DESIGN PRESS 155 (BARG)
36 TEST PRESS (BARG): HELIUM HYDRO 1.5x MWP
37 MAX OPER. TEMP. 177 °C MIN. OPER. TEMP. -35 °C
38 MAX NO. OF IMPELLERS FOR CASING 4-5 depends on Appl
39 MAX CASING CAPACITY (m³/h) 90000
40 CASING SPLIT SEALING (2.2.10) O-ring
41 SYSTEM RELIEF VALVE SET PT. (2.2.4) _____ (MPaG)(assumed)
42 **DIAPHRAGMS:**
43 MATERIAL Stl ASTM A36; Gray Iron ASTM A48 CI 40C
44 **IMPELLERS:**
45 NO. 2 DIAMETERS 766.65
46 NO. VANES EA. IMPELLER 17 (prel)
47
48 **REMARKS** Materials are all RR standard, with years of experience.
49 Operating Temperature limits are for normal service-Maximum
50 operating temperature may be modified during detail design
51 Barrier seal plus separation air system is also included.

TYPE (OPEN, ENCLOSED, ETC.) Enclosed
TYPE FABRICATION Welded
MATERIAL Stl Forging, USS T-1, Type C
MAX. YIELD STRENGTH (N) 620
BRINNEL HARDNESS: MAX 293 MIN 248
SMALLEST TIP INTERNAL WIDTH (mm) After design
MAX. MACH. NO. @ IMPELLER EYE After Design
MAX. IMPELLER HEAD @ 100% SPD (N-m/kg) _____
SHAFT:
MATERIAL Stl Forging, ASTM A-668 Cl.L
DIA @ IMPELLERS (mm) 215.9 DIA @ COUPLING (mm) 165.1
SHAFT END: TAPERED CYLINDRICAL
MAX. YIELD STRENGTH (N) 930
SHAFT HARDNESS (BNH)(Rc) 331 BNH Max
SHAFT HARDNESS (BNH)(Rc) 269 BNH Min
BALANCE PISTON:
MATERIAL Stl Plate ASTM A-514.Gr.F/Q AREA Later (mm²)
FIXATION METHOD Shrink Fit + 2 keys
SHAFT SLEEVES : N / A
AT INTERSTG. CLOSE MATL _____
CLEARANCE POINTS
AT SHAFT SEALS MATL _____
 ACCESSIBLE (2.8.2)
LABYRINTHS:
INTERSTAGE
TYPE Renewable MATERIAL Alum AA Alloy 771 T-5
BALANCE PISTON
TYPE Honeycomb MATERIAL SST ASTM A240
Type 321
SHAFT SEALS:
 SEAL TYPE (2.8.3) Tandem Dry Gas Face Seals
 SETTLING OUT PRESSURE (BARG) TBD
 SPECIAL OPERATION (2.8.1)
 SUPPLEMENTAL DEVICE REQUIRED FOR CONTACT
SEALS (2.8.3.2) TYPE _____
 BUFFER GAS SYSTEM REQUIRED (2.8.7) MANIFOLD (3.5.1.6)
 TYPE BUFFER GAS Pri:Filt Process Gas; Sec: N2; Barrier: Air
 BUFFER GAS CONTROL SYSTEM SCHEMATIC BY VENDOR
 PRESSURIZING GAS FOR SUBATMOSPHERIC SEALS (2.8.8)
TYPE SEAL Burgmann PDGS intermed laby, intchgble NDE-DE
INNER OIL LEAKAGE GUAR. (λ /DAY/SEAL) N / A
BUFFER GAS REQUIRED FOR:
 AIR RUN-IN OTHER N2 for run-in
BUFFER GAS FLOW (PER SEAL):
NORM: 7.1 am³/h @ Design (kPa) Δ P 50
MAX. 10.7 am³/h @ Design (kPa) Δ P 100
BEARING HOUSING CONSTRUCTION:
TYPE (SEPARATE, INTEGRAL) Separate SPLIT Vertical
MATERIAL Stl ASTM A668 Cl B; Iron ASTM A48 Cl 40C



ENGINEERS INDIA LIMITED
NEW DELHI

JOB NO. 6988 ITEM NO. _____
 REVISION NO. 0 DATE 6-Apr-08
 PAGE 4 OF 6 BY J. Bygrave

R
E
V

CENTRIFUGAL COMPRESSOR
DATA SHEET (API 617-6TH)
SI UNITS

CONSTRUCTION FEATURES (CONTINUED)

BEARINGS AND BEARING HOUSINGS

| RADIAL | INLET | EXHAUST | THRUST | ACTIVE | INACTIVE |
|--------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|--------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------|
| | <input checked="" type="checkbox"/> TYPE <input checked="" type="checkbox"/> MANUFACTURER <input checked="" type="checkbox"/> LENGTH (mm) <input checked="" type="checkbox"/> SHAFT DIA. (mm) <input checked="" type="checkbox"/> UNIT LOAD (ACT/ALLOW) (Bar) <input checked="" type="checkbox"/> BASE MATERIAL <input checked="" type="checkbox"/> BABBIT THICKNESS (mm) <input checked="" type="checkbox"/> NO. PADS <input checked="" type="checkbox"/> LOAD: B'TWN/ON PAD <input checked="" type="checkbox"/> PIVOT: CTR/OFFSET, % | Tilt-Pad | Tilt-Pad | <input checked="" type="checkbox"/> TYPE <input checked="" type="checkbox"/> MANUFACTURER <input checked="" type="checkbox"/> UNIT LOADING (MAX BAR) <input checked="" type="checkbox"/> UNIT LOAD (ULT.) (BAR) <input checked="" type="checkbox"/> AREA (mm ²) <input checked="" type="checkbox"/> NO. PADS <input checked="" type="checkbox"/> PIVOT: CENTER / OFFSET, % <input checked="" type="checkbox"/> PAD BASE MATL | Self Leveling/Tilting Pad |
| | Waukesha | | Waukesha | Waukesha | |
| | 82.6 | 82.6 | | After Design | After Design |
| | 165.1 | 165.1 | | 44.83 | 44.83 |
| | <5 / 15 | <5 / 15 | | 33226 | 33226 |
| | Steel | Steel | | 9 | 9 |
| | Tin Based > 1.5 | | | Offset 70 % | Offset 70% |
| | 4 | 4 | | Stl / Tin based Babbitt | |
| | Between | Between | LUBRICATION: <input checked="" type="radio"/> FLOODED <input type="radio"/> DIRECTED | | |
| | Center | Center | THRUST COLLAR: <input type="radio"/> INTEGRAL <input checked="" type="radio"/> REPLACEABLE | | |
| | | | MATERIAL <u>Steel Plate AISI 4340</u> | | |

BEARING SPAN 2263 mm

BEARING TEMPERATURE DEVICES SEE ATTACHED API-670 DATA SHT

THERMISTORS

TYPE POS TEMP COEFF NEG TEMP COEFF

TEMP SWITCH & INDICATOR BY: PURCH MFR

THERMOCOUPLES

SELECTOR SWITCH & INDIC. BY: PURCH MFR

RESISTANCE TEMP DETECTORS

RESISTANCE MAT'L Platinum 100 OHMS

SELECTOR SWITCH & INDICATOR BY: PURCH X MFR

LOCATION-JOURNAL BRG

NO. EA PAD EVERY OTH PAD 2 PER BRG

OTHER

LOCATION-THRUST BRG

NO. EA PAD EVERY OTH PAD 2 PER BRG

OTHER

NO. (INACT) EA PAD EVERY OTH PAD 2 PER BRG

OTHER

MONITOR SUPPLIED BY (3.4.7.4) Rolls-Royce

LOCATION UCP ENCLOSURE

MFR. Rolls-Royce MODEL 3500

SCALE RGE ALARM SET @ 120 °C

SHTDWN SET @ 130 °C TIME DELAY 1 SEC

SEE ATTACHED API-670 DATA SHEET

VIBRATION DETECTORS:

TYPE Non-Contacting MODEL 3300 XL

MFR Bently-Nevada

NO. AT EA SHAFT BEARING 2 TOTAL NO. 4

OSCILLATOR-DETECTORS SUPPLIED BY Rolls-Royce

MFR Bently-Nevada MODEL 3300 XL

MONITOR SUPPLIED BY (3.4.7.2)

LOCATION UCP ENCLOSURE

MFR. Bently-Nevada MODEL 3500

SCALE RGE ALARM SET @ 60 um

SHTDWN: SET @ 90 um TIME DELAY 1 SEC

SEE ATTACH. API-670 DATA SHEET

AXIAL POSITION DETECTOR:

TYPE Non-Contacting MODEL 3300 XL

MFR Bently-Nevada NO. REQUIRED 2

OSCILLATOR-DEMODULATOR SUPPLIED BY Rolls-Royce

MFR Bently-Nevada MODEL 3300 XL

MONITOR SUPPLIED BY (3.4.7.2) Rolls-Royce

LOCATION UCP ENCLOSURE

MFR. Bently-Nevada MODEL 3500

SCALE RGE ALARM SET @ +/- .5 um

SHTDWN: SET @ +/- .65 um TIME DELAY 1 SEC

CASING CONNECTIONS

| CONNECTION | DESIGN APPROVAL REQ'D (2.11.2.10) | ASME API605 OTHERS SIZE | FACING | POSITION (2.4.2.1) | FLANGED OR STUDDED (2.4.2.1) | MATING FLG & GASKET BY VENDOR (2.4.2.3) | GAS VELOCITY m/SEC |
|------------|-----------------------------------|-------------------------|--------|--------------------|------------------------------|-----------------------------------------|--------------------|
| INLET | No | 914.4mm 900# | RF | Horiz/Side | Flanged | Yes | 14.50 |
| DISCHARGE | No | 914.4mm 900# | RF | Horiz/Side | Flanged | Yes | 11.99 |

REMARKS

Dimensions indicated (diameters and lengths) are typical for normal service - actual dimensions are subject to design review

Vibration and position detector settings are typical

Axial position alarm and shutdown setting is equal to the measured thrust bearing axial clearance plus the indicated value.



ENGINEERS INDIA LIMITED
NEW DELHI

**R
E
V**

CENTRIFUGAL COMPRESSOR
DATA SHEET (API 617-6TH)
SI UNITS

JOB NO. 6988 ITEM NO. _____
REVISION NO. 0 DATE 6-Apr-08
PAGE 5 OF 6 BY J. Bygrave

| OTHER CONNECTIONS | | | |
|--------------------------|-----|---------|-------------------|
| SERVICE: | NO. | SIZE | TYPE |
| LUBE-OIL INLET | 2 | 1"1" | NPTF/3000#SAE |
| LUBE OIL OUTLET | 4 | 1"-2" | 3000#SAE |
| SEAL-OIL INLET | | | |
| SEAL-OIL OUTLET | | | |
| SEAL GAS INLET | 2 | .75" | 3000# SAE |
| SEAL GAS OUTLET | 2 | .75" | 3000# SAE |
| CASING DRAINS | 2 | .75" | 3000# SAE |
| STAGE DRAINS | | | |
| VENTS | 2 | .75"-2" | 3000# SAE |
| VENTS | | | |
| PRESSURE | 4 | 1" | NPTF, 2 each nozz |
| TEMPERATURE | 8 | 1" | NPTF, 4 each nozz |
| SOLVENT INJECTION | | | |
| PURGE FOR: | | | |
| BRG. HOUSING | | | |
| BTWN BRG & SEAL | 2 | .75" | 3000# SAE |
| BTWN SEAL & GAS | 2 | .75" | 3000# SAE |

INDIVIDUAL STAGE DRAINS REQUIRED (2.4.3.2)
 VALVED & BLINDED
 VALVED & BLINDED & MANIFOLD 2 Casing drains
 KEY PHASOR REQUIRED
 COMPRESSOR GEAR DRIVER

ALLOWABLE PIPING FORCES AND MOMENTS:

| INLET | | DISCHARGE | | | |
|-------------------------------------------------------------------------------------------------------|------|-----------|------|-------|------|
| FORCE | MOMT | FORCE | MOMT | FORCE | MOMT |
| N | N-m | N | N-m | N | N-m |
| AXIAL VERTICAL HORIZ. 90 Per Rolls-Royce Standard GER 0123 para 3.2, ref Fig 4 & Table 7b | | | | | |
| Per Rolls-Royce Standard GER 0123 para 3.2, ref Fig 4 & Table 7b | | | | | |

- ACCELEROMETER(3.4.7.5) N/A
- SEE ATTACHED API-670 DATA SHEET
- TYPE _____ MODEL _____
- MFR _____ NO. REQUIRED _____
- LOCATION _____
- OSCILATOR-DEMODULATORS SUPPLIED BY
- MFR _____ MODEL _____
- MONITOR SUPPLIED BY (3.4.7.6)
- LOCATION _____ ENCLOSURE _____
- MFR _____ MODEL _____
- SCALE RANGE _____ ALARM SET @ _____ mm/SEC²
- SHTDWN SET @ _____ mm/SEC² TIME DELAY _____ SEC

ACCESSORIES

COUPLING AND GUARDS (3.2)
 NOTE: SEE ROTATING ELEMENTS - SHAFT ENDS
 SEE ATTACHED API-671 DATA SHEET KEYLESS HYDRAULIC KEYED
 COUPLING FURNISHED BY Rolls-Royce
 MANUFACTURER Bibby or equal TYPE Dry MODEL service factor ≥ 1.75
 COUPLING GUARD FURNISHED BY: Rolls-Royce
 TYPE: FULLY ENCLOSED SEMI-OPEN OTHER non-sparking

COUPLING DETAILS (PREL)

| | | |
|---------------|------------------|----|
| MAX O.D. | 427 | mm |
| HUB WEIGHT | 46 | kg |
| SPACER LENGTH | 1524 (1524 DBSE) | mm |
| SPACER WEIGHT | 163 | kg |

VENDOR MOUNT HALF COUPLING
 LUBRICATION REQUIREMENTS:
 NON-LUBE GREASE CONT. OIL LUBE OTHER
 QUANTITY PER HUB _____ kgs or L/MIN

MOUNTING PLATES
 BASEPLATES: FURNISHED BY (3.3.1.1)
 COMPRESSOR ONLY (3.3.2.1) DRIVER GEAR
 OTHER _____
 DRIP TRIM LEVELING PADS (3.3.2.2)
 COLUMN MOUNTING (3.3.2.3)
 SUB-SOLE PLATES REQ'D (3.3.3.2)
 STAINLESS STEEL SHIM THICKNESS _____ mm
 PRIMER FOR EPOXY GROUT REQ'D (3.3.1.2.9)
 TYPE _____
 BASE PLATE WILL BE ON CONCRETE FOUNDATION (3.3.2.5)
 MACHINED MOUNTING PADS REQ'D. (3.3.2.6)

SOLEPLATES: FURNISHED BY: Rolls-Royce
 THICKNESS _____ mm
 SUBSOLE PLATES REQ'D (3.3.3.2)
 STAINLESS STEEL SHIM THICKNESS - mm
 DRIVER _____ GEAR _____ COMPRESSOR 3.2 mm
 PRIMER FOR EPOXY GROUT REQ'D (3.3.1.2.9)
 TYPE _____

REMARKS
 Number and size of connections is preliminary
 Final quantity and location will be advised after final design
 is complete.
 Foundation bolts by Rolls-Royce



ENGINEERS INDIA LIMITED
NEW DELHI

R
E
V

CENTRIFUGAL COMPRESSOR
DATA SHEET (API 617-6TH)
SI UNITS

JOB NO. 6988 ITEM NO. _____
REVISION NO. 0 DATE 6-Apr-08
PAGE 6 OF 6 BY J. Bygrave

UTILITIES

● **UTILITY CONDITIONS:** (see R-R proposal)

| STEAM: | N / A | DRIVERS | HEATING |
|--------------|-------|---------------------|---------------------|
| INLET MIN | _____ | BARG(kPaG) _____ °C | BARG(kPaG) _____ °C |
| NORM | _____ | BARG(kPaG) _____ °C | BARG(kPaG) _____ °C |
| MAX | _____ | BARG(kPaG) _____ °C | BARG(kPaG) _____ °C |
| EXHAUST. MIN | _____ | BARG(kPaG) _____ °C | BARG(kPaG) _____ °C |
| NORM | _____ | BARG(kPaG) _____ °C | BARG(kPaG) _____ °C |
| MAX | _____ | BARG(kPaG) _____ °C | BARG(kPaG) _____ °C |

ELECTRICITY: (3.4.6.1)

| | DRIVERS | HEATING | CONTROL | SHUTDOWN |
|---------|---------|---------|---------|----------|
| VOLTAGE | _____ | _____ | _____ | _____ |
| HERTZ | _____ | _____ | _____ | _____ |
| PHASE | _____ | _____ | _____ | _____ |

COOLING WATER: N / A

| | | | |
|---------------|------------------|------------|----------|
| TEMP. INLET | _____ °C | MAX RETURN | _____ °C |
| PRESS NORM | _____ BARG(kPaG) | | |
| DESIGN | _____ BARG(kPaG) | | |
| MIN RETURN | _____ BARG(kPaG) | | |
| MAX ALLOW Δ P | _____ BAR(kPa) | | |

WATER SOURCE _____

INSTRUMENT AIR:

MAX PRESS _____ BARG(kPaG) MIN PRESS _____ BARG(kPaG)

■ **TOTAL UTILITY CONSUMPTION:**

| | | |
|--------------------------------|------------------------------------|------|
| COOLING WATER | N / A | m³/h |
| STEAM, NORMAL | N / A | kg/h |
| STEAM, MAX | N / A | kg/h |
| INSTRUMENT AIR | Separation seal air - 20 | m³/h |
| HP (DRIVER) | See compressor performance | kW |
| HP (AUXILIARIES) | See P&ID's | kW |
| HEATERS | See P&ID's | KW |
| PURGE (AIR OR N ₂) | Only required for initial start-up | m³/h |

- MISCELLANEOUS:** per RR standards
- **RECOMMENDED STRAIGHT RUN OF PIPE DIAMETERS**
BEFORE SUCTION **Minimum of 3**
 - NOMOGRAPHS REQUIRED FOR EACH SECTION (5.3.3.1.5)
 - **VENDOR'S REVIEW & COMMENTS ON PURCHASER'S PIPING & FOUNDATION (3.5.3.2)** Scope/Responsibility to be agreed pre-order
 - COMPRESSOR TO BE SUITABLE FOR FIELD RUN IN ON AIR (2.1.17)
 - PROVISION FOR LIQUID INJECTION (2.1.11)
 - **VENDOR'S REVIEW & COMMENTS ON PURCHASER'S CONTROL SYSTEMS (3.4.1.1)**
 - EXTENT OF PROCESS PIPING BY VENDOR (3.5.3.1)
 - SHOP FITUP OF VENDOR PROCESS PIPING (4.4.3.11)
 - **WELDING HARDNESS TESTING (4.2.1.6)**
 - _____
 - **VENDOR'S REPRESENTATIVE SHALL (2.1.14)**
 - OBSERVE FLANGE PARTING
 - CHECK ALIGNMENT AT TEMPERATURE
 - BE PRESENT AT INITIAL ALIGNMENT

SHOP INSPECTION AND TESTS: (4.1.4)

| | REQ'D. | WITN |
|------------------------------------------------------------|--------|------|
| 25 CLEANLINES (4.2.1.5) | ● | ● |
| 26 HYDROSTATIC | ● | ● |
| 27 IMPELLER OVERSPEED | ● | ● |
| 28 MECHANICAL RUN | ● | ● |
| 29 ● CONTRACT COUPLING ○ IDLING ADAPTORS | | |
| 30 ● CONTRACT PROBES ○ SHOP PROBES | | |
| 31 VARY LUBE & SEAL OIL PRESSURES | ● | ● |
| 32 AND TEMPERATURES (4.3.4.2.5) within allowable limits | | |
| 33 POLAR FORM VIB DATA (4.3.4.3.3) Bode plot in polar form | ● | ● |
| 34 VIBRATION DATA RECORDED (4.3.4.3.6) Adre digital data | ● | ● |
| 35 DATA TO PURCHASER (4.3.4.3.7) Adre data via CD | ● | ● |
| 36 SHAFT END SEAL INSP (4.3.4.4.1) | ● | ● |
| 37 GAS LEAK TEST DISCH PRESS (4.3.5.2) | ● | ● |
| 38 ○ BEFORE ● AFTER POST TEST INSPECTION (4.3.6.8) | | |
| 39 PERFORMANCE TEST(GAS)(PTC10 TYPE II)(4.3.6.1) | ● | ● |
| 40 NO LOAD STRING TEST (4.3.6.2) (ONE PER STATION) | ● | ● |
| 41 DIS-ASSEMBLE/RE-ASSEMBLE AFTER TEST (REM-7) | ● | ● |
| 42 DYNAMIC BALANCING OF ROTOR W/O HALF COUPLING | ● | Obs |
| 43 GEAR TEST (4.3.6.4) | ○ | |
| 44 HELIUM LEAK TEST | ○ | |
| 45 SOUND LEVEL SURVEY DURING STRING TEST | ● | ● |
| 46 SHOP VERIFICATION OF UNBALANCED RESPONSE | ● | ● |
| 47 ANALYSIS (@ COUPLING HUB ONLY) (ONE PER STATION) | | |
| 48 COPIES OF CERTIFIED TEST DATA & MATERIALS | ● | |
| 49 RESIDUAL ELECT. & MECH RUN OUT | ● | ● |
| 50 CHECK BEARINGS & SEALS AFTER TEST (REM-7) | ● | ● |
| 51 | ● | ● |

■ **WEIGHTS (kg):**

| | | | | | | | |
|---------------------------------|--------|------|--------|--------|-------|-------|-----------------------------------|
| COMPR. | 46500 | GEAR | _____ | DRIVER | _____ | BASE | _____ |
| ROTORS: | COMPR. | 1125 | DRIVER | _____ | GEAR | _____ | _____ |
| COMPRESSOR COVER | | | | | | | 5500 |
| SOUR SEAL OIL TRAPS | | | | | | | N/A |
| L.O. CONSOLE | | | | | | | S.O. CONSOLE _____ |
| OVERHEAD SEAL OIL TANKS | | | | | | | N/A |
| MAX. FOR MAINTENANCE (IDENTIFY) | | | | | | | Aero and Rotor 10100 |
| TOTAL SHIPPING WEIGHT | | | | | | | Compressor + Pipe and Elect 49500 |


■ **SPACE REQUIREMENTS (mm):** (See R-R Proposal)

| | | | |
|-------------------------|---------|---------|---------|
| COMPLETE UNIT: | L _____ | W _____ | H _____ |
| L.O. CONSOLE: | L _____ | W _____ | H _____ |
| S.O. CONSOLE: | L _____ | W _____ | H _____ |
| SOUR SEAL OIL TRAPS | _____ | | |
| OVERHEAD SEAL OIL TANKS | _____ | | |


SEE INSTALLATION SECTION OF PROPOSAL

- REMARKS:**
- 5) Spare rotor will receive mech run test
 - 6) No load string test shall be carried out for one GTC package per station
 - 7) Post test inspection of the dry gas seal and bearing shall be carried during the spare rotor changeout only. DGS inspection as per Burgmann instructions


GAIL Pipeline Expansion Project Feb 24'09
RF36-2 MW 17.393 Pd 99.930 kG/cm².g TI 34.50 °C



GAIL Pipeline Expansion Project Feb 24'09
RF36-2 MW 17.393 PI 74.100 kg/cm².g TI 34.50 °C



GAIL Pipeline Expansion Project Feb 24'09
RF36-2 MW 17.074 Pd 99.930 kg/cm².g TI 34.40 °C




CompPerform[1.79]
PLAN: Chai nsa


UNIT SPECIFIED


SECTION 1


GAIL Pipeline Expansion Project Feb 24'09
RF36-2 MW 17.074 PI 74.500 kg/cm².g TI 34.40 °C



GAIL Pipeline Expansion Project Feb 24'09
RF36-2 MW 17.074 Pd 99.930 kg/cm².g TI 34.40 °C



|  ENGINEERS INDIA LIMITED NEW DELHI | JOB NO. <u>6988</u> ITEM NO. _____ PURCHASE ORDER NO. _____ SPECIFICATION NO <u>6988-000-KA-MR-5010</u> REVISION NO. <u>0</u> DATE <u>5-Apr-09</u> PAGE <u>1</u> OF <u>10</u> BY <u>Leong, HT</u> | R E V | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|--------------------------|---------------------|---------------------|-------------------------------------------------------|----|-------|----|---|---------------------------------------------------------|----|-------|----|----|--------------------------------------------------|-------|-------|-------|-------|----------------------------------------------|-------|-------|-------|-------|----------------------------------------------------------|-------|-------|-------|-------|----------------------------------------------------------------|-------|-------|-------|-------|---------------------------------------------|-------|-------|-------|-------|-----------------------------------------------------|-------|-------|-------|-------|---------------------------------------------------|-------|-------|-------|-------|------------------------------------------------------|-------|-------|-------|-------|-------------------------------------------------|-------|-------|-------|-------|------------------------------------------------------------|-----|-------|-------|-------|--------------------------------------------------------------------------------------|-------|-------|-------|-------|------------------------------------------------------------------------------------------------------------------|-------|-------|-------|-------|-----------------------------------------------|-------|-------|-------|-------|-----------------------------------------------|-------|-------|-------|-------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| COMBUSTION GAS TURBINE (API 616-4TH) DATA SHEET SI UNITS | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 1 APPLICABLE TO: <input checked="" type="radio"/> PROPOSAL <input type="radio"/> PURCHASE <input type="radio"/> AS BUILT 2 FOR <u>GAIL (INDIA) LIMITED</u> UNIT <u>PIPELINE EXPANSION PROJECT</u> 3 SITE <u>CHAINSA STATION</u> SERIAL NO. _____ 4 SERVICE <u>GAS COMPRESSOR</u> NO. REQUIRED <u>TWO (2)</u> 5 <input checked="" type="radio"/> CONTINUOUS <input type="radio"/> INTERMITTENT <input type="radio"/> STANDBY DRIVEN EQUIP. <u>CENTRIFUGAL COMPRESSOR</u> 6 MANUFACTURER <u>Rolls-Royce</u> <input checked="" type="radio"/> MODEL <u>RB211-GT61 DLE</u> ISO RATING <u>32,987</u> kW @ <u>4850</u> RPM 7 NOTE: INFORMATION TO BE COMPLETED: <input type="radio"/> BY PURCHASER <input type="checkbox"/> BY MANUFACTURER <input checked="" type="checkbox"/> BY MFR IF NOT BY PURCHASER | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| GENERAL | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 9 CYCLE: <input type="radio"/> REGEN <input checked="" type="radio"/> SIMPLE <input type="radio"/> EXHAUST HEAT RECOVERY TYPE: <input type="checkbox"/> SINGLE SHAFT <input checked="" type="checkbox"/> MULTI SHAFT 10 DRIVEN EQUIPMENT: NORMAL SHAFT, kW _____ @ _____ RPM RATED SHAFT (KW) _____ @ _____ RPM 11 OUTPUT SHAFT SPEED RANGE (4.1.5) <input checked="" type="checkbox"/> MIN <u>3152</u> <input checked="" type="checkbox"/> MAX <u>5090</u> RPM 12 DESIRED MINIMUM SITE POWER _____ kW @ _____ RPM <input checked="" type="checkbox"/> ENCLOSURE REQUIRED 13 OPERATION <input checked="" type="radio"/> ATTENDED <input type="radio"/> UNATTENDED <input type="checkbox"/> POTENTIAL MAXIMUM POWER (3.33) _____ Kw | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PERFORMANCE | | LOCATION (4.1.19) | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 15 GAS TURBINE INCLUDING ALL LOSSES <table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th></th> <th style="text-align: center;">SITE RATED (3.45)</th> <th style="text-align: center;">NORMAL DUTY (3.26)</th> <th style="text-align: center;">SITE MAX TEMP</th> <th style="text-align: center;">SITE MIN TEMP</th> </tr> </thead> <tbody> <tr> <td>19 <input checked="" type="radio"/> DRY BULB TEMP, °C</td> <td style="text-align: center;">45</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">45</td> <td style="text-align: center;">0</td> </tr> <tr> <td>20 <input checked="" type="radio"/> RELATIVE HUMIDITY %</td> <td style="text-align: center;">84</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">84</td> <td style="text-align: center;">37</td> </tr> <tr> <td>21 <input checked="" type="radio"/> ALTITUDE (m)</td> <td style="text-align: center;">197.8</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">197.8</td> <td style="text-align: center;">197.8</td> </tr> <tr> <td>22 <input type="checkbox"/> OUTPUT, (KW) (1)</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> </tr> <tr> <td>23 <input type="checkbox"/> HEAT RATE, LHV, MJ/ KW-HR</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> </tr> <tr> <td>24 <input checked="" type="checkbox"/> OUTPUT SHAFT SPEED, RPM</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> </tr> <tr> <td>26 <input type="checkbox"/> AIR FLOW kg/SEC</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> </tr> <tr> <td>27 <input type="checkbox"/> EXHAUST FLOW kg/SEC (1)</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> </tr> <tr> <td>28 <input type="checkbox"/> FIRING TEMPERATURE °C</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> </tr> <tr> <td>29 <input type="checkbox"/> GAS GEN. EXHAUST TEMP °C</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> </tr> <tr> <td>30 <input type="checkbox"/> PT EXHAUST TEMP. °C</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> </tr> <tr> <td>31 <input checked="" type="radio"/> CERTIFIED POINT (3.26)</td> <td style="text-align: center;">YES</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> </tr> <tr> <td>32 (1) INCLUDING <input type="radio"/> STEAM <input type="radio"/> WATER EFFECTS FOR</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> </tr> <tr> <td>33 <input checked="" type="checkbox"/> EMISSION CONTROL <input checked="" type="checkbox"/> AUGMENTATION (4.1.9)</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> </tr> <tr> <td>34 <input type="checkbox"/> STEAM FLOW, kg/HR</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> </tr> <tr> <td>35 <input type="checkbox"/> WATER FLOW, m³/HR</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> </tr> </tbody> </table> | | | SITE RATED (3.45) | NORMAL DUTY (3.26) | SITE MAX TEMP | SITE MIN TEMP | 19 <input checked="" type="radio"/> DRY BULB TEMP, °C | 45 | _____ | 45 | 0 | 20 <input checked="" type="radio"/> RELATIVE HUMIDITY % | 84 | _____ | 84 | 37 | 21 <input checked="" type="radio"/> ALTITUDE (m) | 197.8 | _____ | 197.8 | 197.8 | 22 <input type="checkbox"/> OUTPUT, (KW) (1) | _____ | _____ | _____ | _____ | 23 <input type="checkbox"/> HEAT RATE, LHV, MJ/ KW-HR | _____ | _____ | _____ | _____ | 24 <input checked="" type="checkbox"/> OUTPUT SHAFT SPEED, RPM | _____ | _____ | _____ | _____ | 26 <input type="checkbox"/> AIR FLOW kg/SEC | _____ | _____ | _____ | _____ | 27 <input type="checkbox"/> EXHAUST FLOW kg/SEC (1) | _____ | _____ | _____ | _____ | 28 <input type="checkbox"/> FIRING TEMPERATURE °C | _____ | _____ | _____ | _____ | 29 <input type="checkbox"/> GAS GEN. EXHAUST TEMP °C | _____ | _____ | _____ | _____ | 30 <input type="checkbox"/> PT EXHAUST TEMP. °C | _____ | _____ | _____ | _____ | 31 <input checked="" type="radio"/> CERTIFIED POINT (3.26) | YES | _____ | _____ | _____ | 32 (1) INCLUDING <input type="radio"/> STEAM <input type="radio"/> WATER EFFECTS FOR | _____ | _____ | _____ | _____ | 33 <input checked="" type="checkbox"/> EMISSION CONTROL <input checked="" type="checkbox"/> AUGMENTATION (4.1.9) | _____ | _____ | _____ | _____ | 34 <input type="checkbox"/> STEAM FLOW, kg/HR | _____ | _____ | _____ | _____ | 35 <input type="checkbox"/> WATER FLOW, m³/HR | _____ | _____ | _____ | _____ | <input type="radio"/> INDOOR <input checked="" type="radio"/> OUTDOOR <input type="radio"/> GRADE <input type="radio"/> HEATED <input checked="" type="radio"/> UNDER ROOF <input type="radio"/> MEZZANINE <input checked="" type="radio"/> UNHEATED <input type="radio"/> PARTIAL SIDES <input checked="" type="radio"/> ONSHORE ELEC. AREA CLASSIFICATION (4.1.14) <input type="radio"/> NON-HAZARDOUS <input checked="" type="radio"/> HAZARDOUS APPLICABLE CODE: <input type="radio"/> NEC500 <input type="radio"/> NEC505 <input checked="" type="radio"/> IEC GROUP <u>IIA</u> CLASS: _____ TEMPERATURE CODE: <u>T3</u> AREA CLASSIFICATION <input type="radio"/> DIVISION <input checked="" type="radio"/> ZONE <u>2</u> <input type="radio"/> THIRD PARTY CERTIFICATION REQUIRED <input type="radio"/> WINTERIZATION REQD <input type="radio"/> <input checked="" type="radio"/> TROPICALIZATION REQD (5.4.6.6) UNUSUAL CONDITIONS: <input checked="" type="radio"/> DUST <input type="radio"/> FUMES <input checked="" type="radio"/> CORROSIVE AGENTS (4.10.1.1) _____ <input checked="" type="radio"/> SO2 ANNUAL MEAN - 6.01mg/m3, 24hr max - 10.66mg/m3 <input checked="" type="radio"/> OTHER (5.5.3.4) ONSHORE OIL&GAS NOISE SPECIFICATIONS: (4.1.10) <input checked="" type="radio"/> APPLICABLE TO MACHINE: (5.7.4.1) SEE SPECIFICATION <u>88</u> dBA at 1 meter <input type="radio"/> APPLICABLE TO NEIGHBORHOOD: (5.7.4.2) SEE SPECIFICATION _____ |
| | SITE RATED (3.45) | NORMAL DUTY (3.26) | SITE MAX TEMP | SITE MIN TEMP | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 19 <input checked="" type="radio"/> DRY BULB TEMP, °C | 45 | _____ | 45 | 0 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 20 <input checked="" type="radio"/> RELATIVE HUMIDITY % | 84 | _____ | 84 | 37 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 21 <input checked="" type="radio"/> ALTITUDE (m) | 197.8 | _____ | 197.8 | 197.8 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 22 <input type="checkbox"/> OUTPUT, (KW) (1) | _____ | _____ | _____ | _____ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 23 <input type="checkbox"/> HEAT RATE, LHV, MJ/ KW-HR | _____ | _____ | _____ | _____ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 24 <input checked="" type="checkbox"/> OUTPUT SHAFT SPEED, RPM | _____ | _____ | _____ | _____ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 26 <input type="checkbox"/> AIR FLOW kg/SEC | _____ | _____ | _____ | _____ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 27 <input type="checkbox"/> EXHAUST FLOW kg/SEC (1) | _____ | _____ | _____ | _____ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 28 <input type="checkbox"/> FIRING TEMPERATURE °C | _____ | _____ | _____ | _____ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 29 <input type="checkbox"/> GAS GEN. EXHAUST TEMP °C | _____ | _____ | _____ | _____ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 30 <input type="checkbox"/> PT EXHAUST TEMP. °C | _____ | _____ | _____ | _____ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 31 <input checked="" type="radio"/> CERTIFIED POINT (3.26) | YES | _____ | _____ | _____ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 32 (1) INCLUDING <input type="radio"/> STEAM <input type="radio"/> WATER EFFECTS FOR | _____ | _____ | _____ | _____ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 33 <input checked="" type="checkbox"/> EMISSION CONTROL <input checked="" type="checkbox"/> AUGMENTATION (4.1.9) | _____ | _____ | _____ | _____ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 34 <input type="checkbox"/> STEAM FLOW, kg/HR | _____ | _____ | _____ | _____ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 35 <input type="checkbox"/> WATER FLOW, m³/HR | _____ | _____ | _____ | _____ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 37 APPLICABLE SPECIFICATIONS: 38 <input checked="" type="radio"/> API 616 GAS TURBINES FOR THE PETROLEUM,CHEMICAL, & GAS INDUSTRY SERVICES 39 <input type="radio"/> GOVERNING SPECIFICATION (IF DIFFERENT) _____ 40 _____ 41 _____ 42 <input checked="" type="radio"/> VENDOR HAVING UNIT RESPONSIBILITY (4.1.2) _____ 43 <u>Rolls-Royce</u> | | PAINTING: <input checked="" type="radio"/> MANUFACTURER'S OFFSHORE STD. <input type="radio"/> OTHER _____ NOTE: All Data Sheets References to GG=Gas Generator SS = Single Shaft and PT = Power Turbine REMARKS: <u>Also see Rolls-Royce Deviations to API 616</u> _____ _____ _____ _____ _____ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 44 SHIPMENT: (6.4) 45 <input type="radio"/> DOMESTIC <input checked="" type="radio"/> EXPORT <input type="radio"/> EXPORT BOXING REQD. 46 <input type="radio"/> OUTDOOR STORAGE MORE THAN 6 MONTHS (6.4.1) 47 SPARE ROTOR ASSEMBLY PACKAGED FOR (6.4.3.10) 48 <input type="radio"/> DOMESTIC <input type="radio"/> EXPORT SHIPMENT 49 COMMENTS: _____ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

| | | | |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------|
|  | ENGINEERS INDIA LIMITED NEW DELHI | SPEC NO. <u>6988-000-KA-MR-501</u> (ITEM NO. REVISION NO. <u>0</u> DATE <u>5-Apr-09</u> PAGE <u>2</u> OF <u>10</u> BY <u>Leong, HT</u> | R E V |
| COMBUSTION GAS TURBINE (API 616-4TH) DATA SHEET SI UNITS | | | |
| FUEL SYSTEM (5.8) | | | |
| 2 TYPE <input checked="" type="radio"/> GAS (5.8.2) <input type="radio"/> LIQUID (5.8.3) <input type="radio"/> DUAL (5.8.1.5.1) | | | |
| 3 DUAL SYSTEM REQMTS (5.8.1.5.1) <input type="radio"/> GAS/GAS <input type="radio"/> GAS/LIQUID <input type="radio"/> LIQUID/LIQUID | | | |
| 4 <input type="radio"/> COMPLETE FUEL RECEIVING SYSTEM (5.8.1.1) <input type="radio"/> MAX. TIME ALLOWED TO COMPLETE TRANSFER _____ SECONDS | | | |
| GAS FUELS (5.8.2) | | LIQUID FUELS (5.8.3) | |
| | | FUEL GRADE (5.8.3.3) | |
| 9 <input checked="" type="radio"/> FUEL ANALYSIS - MOL % (3.7.2.1) (3.7.1.8) | | ASTM D1655 ASTM <input type="radio"/> 0GT <input type="radio"/> 1GT JET <input type="radio"/> A <input type="radio"/> A-1 <input type="radio"/> B D2880 <input type="radio"/> 2GT <input type="radio"/> 3GT <input type="radio"/> 4GT <input type="radio"/> OTHER, INDICATE ANALYSIS BELOW (5.8.3.3 c) | |
| 10 COMPOSITION: M.W. NORMAL STARTING ALT | | LIQUID FUEL TREATMENT REQUIRED <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO | |
| 11 AIR 29 THE FUEL GAS COMPOSITION | | TREATMENT SYSTEM BY (3.7.1.5) <input type="radio"/> VENDOR <input type="radio"/> OTHER | |
| 12 OXYGEN 32 IS AS INDICATED IN THE COMPRESSOR | | FUEL TRANSFER EQP REQUIRED (5.8.1.4.5) <input type="checkbox"/> YES <input type="checkbox"/> NO | |
| 13 NITROGEN 38 PROCESS DATA SHEET | | HEATER REQUIRED (5.8.1.4.4) <input type="checkbox"/> YES <input type="checkbox"/> NO | |
| 14 WATER VAPOR 18 INCLUDED IN THIS SECTION. | | <input type="checkbox"/> LIQ FUEL PRESS REQD, MAX/MIN,(kPaG) _____ / _____ | |
| 15 HYDROGEN SULPHIDE 34 _____ | | FUEL ANALYSIS DATA (5.8.3.3) ASTM MEASURED | |
| 16 CARBON DIOXIDE 44 _____ | | PROPERTY METHOD VALUE | |
| 17 HYDROGEN 2 _____ | | VISCOSITY SSU, 38°C D-445 _____ | |
| 18 METHANE 16 _____ | | DISTILLATION DATA D-86 _____ | |
| 19 ETHYLENE 26 _____ | | 50% RECOVERY °C MAX _____ | |
| 20 ETHANE 30 _____ | | END POINT °C MAX _____ | |
| 21 PROPYLENE 42 _____ | | SULFUR CONTENT %WT. MAX. (SELECT APPL METHOD) | |
| 22 PROPANE 44 _____ | | BOMB METHOD D-129 _____ | |
| 23 I-BUTANE 58 _____ | | LAMP METHOD D-1266 _____ | |
| 24 N-BUTANE 58 _____ | | HIGH-TEMP METHOD D-1552 _____ | |
| 25 I-PENTANE 72 _____ | | CARBON RESIDUE (ON 10% | |
| 26 N-PENTANE 72 _____ | | BOTTOMS) % WT. MAX. _____ | |
| 27 HEXANE 86 _____ | | CONRADSON D-189 _____ | |
| 28 HEPTANE 100 _____ | | RAMSBOTTOM D-524 _____ | |
| 29 TOTAL _____ | | COPPER STRIP CORROSION PLATE D-130 _____ | |
| 30 AVG. MOL. WT. _____ | | 3 HRS AT 100°C MAX | |
| 31 CORS AGENTS (5.8.2.3) PPM _____ | | AROMATIC CONTENT D-1319 _____ | |
| 32 CONTMNTS)5.8.2.2.1) PPM _____ | | ASH CONTENT D-482 _____ | |
| 33 LHV MJ/m³/HR (5.8.2.4) _____ | | SPECIFIC GRAVITY, 15°C D-1298 _____ | |
| 34 FUEL PRESS.MAX/MIN,kPag _____ | | FLASH POINT °C D-56 _____ | |
| 35 FUEL TEMP MAX/MIN °C _____ | | POUR POINT °C D-97 _____ | |
| 36 <input type="checkbox"/> FUEL PRESS/TEMP REQD. | | WATER D-95 _____ | |
| 37 MIN BarA/DegC _____ | | FILTERABLE DIRT. MG/100ML D-2276 _____ | |
| 38 COMPRESSION SYS REQD (5.8.1.2.2) <input type="radio"/> YES <input type="radio"/> NO | | TRACE METALS (ATOMIC | |
| 39 HEATER REQD (5.8.2.1) <input type="checkbox"/> YES <input type="checkbox"/> NO | | ABSORPTION PREFERRED) D-3605 _____ | |
| 40 <input type="radio"/> RATE OF CHANGE OF LHV (5.8.2.4) _____ | | SODIUM _____ | |
| 41 | | POTASSIUM _____ | |
| 42 REMARKS: _____ | | VANADIUM _____ | |
| 43 _____ | | CALCIUM _____ | |
| 44 _____ | | LEAD _____ | |
| 45 _____ | | OTHER METALS _____ | |
| 46 _____ | | LOWER HEATING VALUE MJ/kg D-2382 _____ | |
| FUEL SYSTEM PIPING | | | |
| 49 <input type="radio"/> BY PASS AND VENT VALVE (3.7.1.3) <input checked="" type="checkbox"/> ISOLATION BLOCK VALVES <input checked="" type="checkbox"/> ANSI FLANGE RATING | | | |
| 50 <input type="radio"/> TWIN Y-TYPE STRAINER WITH CONTINUOUS FLOW <input checked="" type="checkbox"/> NACE 2002 MATERIAL STANDARDS (4.10.1.8) | | | |
| 51 <input type="radio"/> TRANSFER VALVE (5.8.1.2.4) | | | |
| 52 | | | |



ENGINEERS INDIA LIMITED
NEW DELHI

COMBUSTION GAS TURBINE (API 616-4TH)
DATA SHEET
SI UNITS

SPEC NO. 6988-000-KA-MR-501 (ITEM NO.)

REVISION NO. 0 DATE 5-Apr-09

PAGE 3 OF 10 BY Leong, HT

R
E
V

CONSTRUCTION FEATURES (NOTE 1)

SPEEDS: (POWER TURBINE)

MAX. CONT. 5090 RPM TRIP 5335 RPM

LATERAL CRITICAL SPEEDS (DAMPED)

FIRST CRITICAL _____ RPM _____ MODE

SECOND CRITICAL _____ RPM _____ MODE

THIRD CRITICAL _____ RPM _____ MODE

FOURTH CRITICAL _____ RPM _____ MODE

PROTOTYPE OR MODIFIED ROTOR SUPPORT (4.7.3.5)

LATERAL ANALYSIS REQUIRED (INDIVIDUAL COMPONENTS) (D.1.3)

TRAIN TORSIONAL ANALYSIS REQUIRED (2.7.4.5)

TORSIONAL CRITICAL SPEEDS:

FIRST CRITICAL Per API 616 _____ RPM

SECOND CRITICAL Per API 616 _____ RPM

THIRD CRITICAL _____ RPM

FOURTH CRITICAL _____ RPM

VIBRATION: (4.7.4.5) (7.2.3 o):

ALLOWABLE TEST LEVEL : SHAFT PT: 50 MICRONS P/P

CASE GG: 16 mm/sec

MATERIALS OF CONSTRUCTION (4.10)

COMPRESSOR ROTOR BLADES Titanium Alloy, FV.535, Inco 738 & 718, Nimonic 105

COMPRESSOR STATOR VANES Jethete 152 & EAX, Inco 718, Nimonic 105

SHAFT Steel BLADE/VANE COATING Sermetal 5375 & Waspaloy

| TURBINE STAGE | NOZZLES | BLADES | WHEELS OR DISCS |
|---------------|-----------|---------|-----------------|
| 1 (GG) | Mar-M-002 | CMSX-4 | Waspaloy |
| 2 (GG) | C.1023 | CMSX-4 | Incoloy 901 |
| 3 | | | |
| 1 (PT) | Rene'80 | Rene'80 | 901 |
| 2 (PT) | U-500 | U-500 | 901 |
| 3 (PT) | N-155 | U-500 | 901 |

COMBUSTORS C.263 and Nimonic 75

COMPRESSOR CASING Aluminum Alloy, Jethete EAX, Inco 907/904

COMBUSTOR CASING Jethete 152

TURBINE CASING GG: Nimonic P.E. 16, PT: Waspaloy, Inconel 718

ROTATION, VIEWED FROM DRIVE END CW CCW

GAUGE BOARDS AND CONTROL PANELS

AIR COMPRESSOR:

STAGES 7IP, 6HP MAX. TIP SPEED 5.85 m/SEC

TYPE Axial PRESSURE RATIO 21:1

CASING SPLIT (2.2.3) AXIAL RADIAL

ROTOR SOLID BUILT UP

GAUGE BOARDS

LOCATION _____

CONTROL PANELS (5.4.5.1.1) ON-SKID OFF SKID LOCAL

OFF SKID REMOTE

WEATHER PROTECTION REQUIRED YES NO

SPECIFICATION _____

ANNUNCIATOR REQUIRED (5.4.4.8.5)

VISUAL DISPLAY UNIT (VDU) KEYBOARD

TURBINE:

STAGES 1HP, 1LP, 3PT MAX. TIP SPEED 8.65(GG), 7.3(PT) m/SEC

CASING SPLIT (4.2.3) AXIAL (GG) RADIAL (PT)

ROTOR SOLID BUILT UP

COMBUSTORS: (4.3.2)

SINGLE MULTIPLE, NUMBER 9

GAS LIQUID DUAL FUEL

MAX. ALLOW TEMP. VARIATION +/-150 °C

APPLICABLE PLANE _____

FUEL NOZZLES PER COMBUSTOR 3

WOBBE INDEX NO REQD (4.3.7) MAX _____ MIN _____

CONTROL SYSTEMS

TYPE (5.4.1.5)

MECH PNEU HYDRA ELECTRIC ELECTRONIC

MICROPROCESSOR BASED COMBINED

SIGNAL SOURCE 4-20 mA, 24 V dc

SENSITIVITY _____ RANGE _____ TO _____

TIME OF AC OUTAGE RIDEOUT _____ MIN (5.4.1.6)

SHUT OFF VALVES FOR SHUT DOWN SENSORS (5.4.4.9)

STARTING SYSTEM (5.4.2.1)

MANUAL SEMI AUTOMATIC AUTOMATIC

PURGE (5.4.2.2) _____ MINUTES

SEPARATE SHUTDOWN VALVE TEST DURING OPERATION

MAINTENANCE INTERVALS, HOURS

HOT GAS PATH INSPECTIONS See Note 2

MAJOR OVERHAULS See Note 3

OTHER See Note 4

GOVERNOR (5.4.3)

MFR'S STD. OTHER MAKE _____ MODEL _____

CONSTANT SPEED VARIABLE SPEED

ISOCHRONOUS DROOP

REMOTE SHUTDOWN SIGNAL ELECTRIC

PNEUMATIC HYDRAULIC NONE

MANUAL SPEED CHANGER RPM 5090 MAX. 4610 MIN.

MAINTAIN TURBINE SPEED UPON FAILURE OF CONTROL SIGNAL OR ACTUATOR

NOTE (1) FOR MULTIPLE SHAFT TURBINES, COMPLETE ALL APPLICABLE PORTIONS FOR EACH SHAFT

REMARKS: (2) Half Life refurbishment required generally after 25,000 hours of operation; (3) Major overhaul of GG on condition (generally 50,000 hrs. operation); (4) Borescope Inspection recommended generally after 4,000 hrs operation



ENGINEERS INDIA LIMITED
NEW DELHI

COMBUSTION GAS TURBINE (API 616-4TH)
DATA SHEET
SI UNITS

SPEC NO. 6988-000-KA-MR-501(ITEM NO. _____)

REVISION NO. 0 DATE 5-Apr-09

PAGE 4a OF 10 BY Leong, HT

R
E
V

| 1 CONSTRUCTION FEATURES CONTINUED (NOTE 1) | | | | | |
|---------------------------------------------------------------------------|--------------------------------------------------------------------------------------|---------------|----------------------------------------------------------------------------------------------------------|-----------------------------------------------------------|---------------|
| 2 RB211 GAS GENERATOR BEARINGS AND BEARING HOUSINGS (4.8) | | | | | |
| 3 RADIAL (ROLLER, SQUEEZE-FILM TYPE) | HP & IP Turbine | IP Compressor | THRUST (LOCATION TYPE) | IP Compressor | HP Compressor |
| 4 <input checked="" type="checkbox"/> TYPE | Anti-Friction | Anti-Friction | <input checked="" type="checkbox"/> TYPE | Anti-Friction | Anti-Friction |
| 5 <input checked="" type="checkbox"/> MANUFACTURER | RHP/FAG (TYP) | RHP (TYP) | <input checked="" type="checkbox"/> MANUFACTURER | RHP/FAG (TYP) | RHP (TYP) |
| 6 <input checked="" type="checkbox"/> BEARING WIDTH, mm | 39.6 | 24.3 | <input checked="" type="checkbox"/> BEARING WIDTH, mm | 63.4 | 76.2 |
| 7 <input checked="" type="checkbox"/> OUTER/INNER DIAMETER, mm | 254.4 / 221.6 | 285.5 / 252.1 | <input checked="" type="checkbox"/> OUTER/INNER DIAMETER, mm | 215.9 / 139.7 | 215.8 / 127.0 |
| 8 <input type="checkbox"/> UNIT LOAD (ACT/ALLOW) kPa | | | <input type="checkbox"/> UNIT LOAD (MAX POTEN.), kPa | | |
| 9 <input checked="" type="checkbox"/> OUTER RACE MATERIAL | AMS6491 | AMS6491 | <input checked="" type="checkbox"/> OUTER RACE MATERIAL | MSRR6113 | MSRR6083 |
| 10 <input checked="" type="checkbox"/> ROLLER MATERIAL | AMS6491 | AMS6491 | <input checked="" type="checkbox"/> ROLLER MATERIAL | MSRR6113 | MSRR6083 |
| 11 <input checked="" type="checkbox"/> CAGE MATERIAL | AMS6415 | AMS6415 | <input checked="" type="checkbox"/> CAGE MATERIAL | MSRR6083 | MSRR6013 |
| 12 <input type="checkbox"/> LOAD: BETWEEN/ON PAD | | | <input checked="" type="checkbox"/> L10 LIFE (On Condition), h | >50,000 | >50,000 |
| 13 <input type="checkbox"/> PIVOT: CENTER/OFFSET, % | | | LUBRICATION: <input type="checkbox"/> FLOODED <input checked="" type="checkbox"/> SCAVENGE SYSTEM | | |
| 14 <input type="checkbox"/> DAMPER BEARING | | | THRUST COLLAR: <input type="checkbox"/> INTEGRAL <input checked="" type="checkbox"/> REPLACEABLE | | |
| 15 <input checked="" type="checkbox"/> L10 LIFE (On Condition), h | >50,000 | >50,000 | BEARING MATERIAL | | |
| 16 BEARING TEMPERATURE DEVICES (4.8.5.5) | <input type="checkbox"/> SEE ATTACHED API-670 DATA SHEET | | VIBRATION DETECTORS: (4.8.5.3) | <input type="checkbox"/> SEE ATTACHED API-670 DATA SHEET | |
| 17 <input type="checkbox"/> THERMOCOUPLES | | | RADIAL VIBRATION DETECTORS | | |
| 18 <input type="checkbox"/> SELECTOR SWITCH & IND. BY: PURCH MFR | | | <input type="checkbox"/> TYPE | <input checked="" type="checkbox"/> MODEL | |
| 19 <input type="checkbox"/> RESISTANCE TEMP DETECTORS | | | <input checked="" type="checkbox"/> MFR | | |
| 20 <input type="checkbox"/> RESISTANCE MATL <input type="checkbox"/> OHMS | | | <input type="checkbox"/> NO. AT EACH SHAFT BEARING | TOTAL NO. | |
| 21 <input type="checkbox"/> SELECTOR SWITCH & IND. BY: PURCH MFR | | | <input type="checkbox"/> OSCILLATOR-DEMODULATOR SUPPLIED BY | | |
| 22 <input type="checkbox"/> LOCATION-JOURNAL BEARING | | | <input type="checkbox"/> MFR | <input type="checkbox"/> MODEL | |
| 23 NUMBER EA PD EVERY OTH PAD PER BRG | | | <input type="checkbox"/> MONITOR SUPPLIED BY (5.4.7.8.2) | | |
| 24 OTHER | | | <input type="checkbox"/> LOCATION | ENCLOSURE | |
| 25 <input type="checkbox"/> LOCATION-THRUST BEARING | | | <input type="checkbox"/> MFR | <input type="checkbox"/> MODEL | |
| 26 NO. (ACT) EA PD EVERY OTH PAD PER BRG | | | <input type="checkbox"/> SCALE RGE | <input type="checkbox"/> ALARM SET @ uM | |
| 27 OTHER | | | <input type="checkbox"/> SHTDOWN <input type="checkbox"/> SET @ uM | <input type="checkbox"/> TIME DELAY SEC | |
| 28 NO. (INACT) EA PD EVERY OTH PAD PER BRG | | | AXIAL POSITION DETECTOR (4.8.5.3): | NOT REQUIRED | |
| 29 OTHER | | | <input type="checkbox"/> SEE ATTACHED API-670 DATA SHEETS | | |
| 30 <input type="checkbox"/> MONITOR SUPPLIED BY (5.4.7.5) | | | <input type="checkbox"/> TYPE | <input checked="" type="checkbox"/> MODEL | |
| 31 <input type="checkbox"/> LOCATION | ENCLOSURE | | <input checked="" type="checkbox"/> MFR | <input type="checkbox"/> NO. REQUIRED | |
| 32 <input type="checkbox"/> MFR | <input type="checkbox"/> MODEL | | <input type="checkbox"/> OSCILLATOR-DEMODULATOR SUPPLIED BY | | |
| 33 <input type="checkbox"/> SCALE RGE | <input type="checkbox"/> ALARM SET @ °C | | <input type="checkbox"/> MFR | <input type="checkbox"/> MODEL | |
| 34 <input type="checkbox"/> SHTDOWN <input type="checkbox"/> SET @ °C | <input type="checkbox"/> TIME DLY SEC | | <input type="checkbox"/> MONITOR SUPPLIED BY (3.4.7.8.2) | | |
| 35 REMARKS: | | | <input type="checkbox"/> LOCATION | ENCLOSURE | |
| 36 | | | <input type="checkbox"/> MFR | <input type="checkbox"/> MODEL | |
| 37 | | | <input type="checkbox"/> SCALE RGE | <input type="checkbox"/> ALARM SET @ uM | |
| 38 | | | <input type="checkbox"/> SHTDOWN <input type="checkbox"/> SET @ uM | <input type="checkbox"/> TIME DELAY SEC | |
| 39 | | | ACCELERATION TRANSDUCERS | | |
| 40 | | | <input type="checkbox"/> SEE ATTACHED API-670 DATA SHEETS | | |
| 41 | | | <input checked="" type="checkbox"/> MFR Vibrometer Inc. | <input checked="" type="checkbox"/> MODEL CE135 | |
| 42 | | | <input checked="" type="checkbox"/> LOCATION GG Casing | <input checked="" type="checkbox"/> NUMBER 3 | |
| 43 | | | <input checked="" type="checkbox"/> MONITOR SUPPLIED BY (3.4.7.8.4) | Rolls-Royce | |
| 44 | | | <input checked="" type="checkbox"/> LOCATION UCP | ENCLOSURE | |
| 45 | | | <input checked="" type="checkbox"/> MFR Bently-Nevada | <input checked="" type="checkbox"/> MODEL 3500 | |
| 46 | | | <input type="checkbox"/> SCALE RGE | <input checked="" type="checkbox"/> ALARM SET @ < 25 mm/s | |
| 47 | | | <input checked="" type="checkbox"/> SHTDOWN <input checked="" type="checkbox"/> SET @ 40 mm/s | <input checked="" type="checkbox"/> TIME DELAY 0 SEC | |
| 48 NOTES | (1) FOR MULTIPLE SHAFT TURBINES, COMPLETE ALL APPLICABLE PORTIONS FOR EACH SHAFT | | | | |
| 49 | (2) FOR THREE BEARING SHAFTS, USE A SEPARATE SHEET FOR THE EXTRA BEARING | | | | |
| 50 | (3) FOR ROLLING ELEMENT BEARINGS, MODIFY ENTRIES AS REQUIRED. SHOW L-10 BEARING LIFE | | | | |



ENGINEERS INDIA LIMITED
NEW DELHI

COMBUSTION GAS TURBINE (API 616-4TH)
DATA SHEET
SI UNITS

SPEC NO. 6988-000-KA-MR-501 (ITEM NO. _____)

REVISION NO. 0 DATE 5-Apr-09

PAGE 4b OF 10 BY Leong, HT

R
E
V

CONSTRUCTION FEATURES CONTINUED (NOTE 1)

RT61 POWER TURBINE BEARINGS AND BEARING HOUSINGS (4.8)

| RADIAL (NOTES 2 AND 3) | | DISC | CPLG | THRUST (NOTE 3) | ACTIVE | INACTIVE |
|---------------------------------------------------------------|---------------|---------------|--------------------------------------------------------------------------------------------------|-----------------|----------|----------|
| <input checked="" type="checkbox"/> TYPE | TILT PAD | TILT PAD | <input checked="" type="checkbox"/> TYPE | TILT PAD | Collar | |
| <input checked="" type="checkbox"/> MANUFACTURER | KMC | Waukesha | <input checked="" type="checkbox"/> MANUFACTURER | Waukesha (TYP) | Waukesha | |
| <input checked="" type="checkbox"/> LENGTH, mm | 102 | 89 | <input checked="" type="checkbox"/> UNIF LOAD (ULTIMATE), kg | | | |
| <input checked="" type="checkbox"/> SHAFT DIAMETER, mm | 254 | 203 | <input checked="" type="checkbox"/> UNIF LOAD (SITE RATED), kg | 19,047 | N/A | |
| <input checked="" type="checkbox"/> UNIF LOAD (ACT/ALLOW), kg | 21129 / 65834 | 667 / 42569.0 | <input checked="" type="checkbox"/> UNIF LOAD (MAX POTEN.), kg | 50439 | N/A | |
| <input checked="" type="checkbox"/> BASE MATERIAL | Steel | Steel | <input checked="" type="checkbox"/> NO. OF PADS / AREA (mm ²) | 9 / 86451 | 0 / N/A | |
| <input checked="" type="checkbox"/> BABBITT THICKNESS, mm | 5.08 | 1.3 | <input checked="" type="checkbox"/> BASE MATERIAL | Steel | Steel | |
| <input checked="" type="checkbox"/> NO. PADS | 4 | 4 | <input type="checkbox"/> BABBITT THICKNESS, mm | | | |
| <input checked="" type="checkbox"/> LOAD: BETWEEN/ON PAD | Between | Between | <input type="checkbox"/> PIVOT: CENTER/OFFSET, % | | | |
| <input checked="" type="checkbox"/> PIVOT: CENTER/OFFSET, % | 60 | 60 | LUBRICATION: <input checked="" type="checkbox"/> FLOODED <input type="checkbox"/> DIRECTED | | | |
| <input checked="" type="checkbox"/> DAMPER BEARING | YES | NO | THRUST COLLAR: <input type="checkbox"/> INTEGRAL <input checked="" type="checkbox"/> REPLACEABLE | | | |

BEARING TEMPERATURE DEVICES (4.8.5.5) SEE ATTACHED API-670 DATA SHEET

THERMOCOUPLES

SELECTOR SWITCH & IND. BY: _____ PURCH _____ MFR

RESISTANCE TEMP DETECTORS

RESISTANCE MAT'L Platinum 100 OHMS

SELECTOR SWITCH & IND. BY: _____ PURCH MFR

LOCATION-JOURNAL BEARING

NUMBER 1 EA PD EVERY OTH PAD 2 PER BRG

OTHER _____

LOCATION-THRUST BEARING

NO. (ACT) 1 EA PD EVERY OTH PAD 2 PER BRG

OTHER _____

NO. (INACT) EA PD EVERY OTH PAD 2 PER BRG

OTHER NONE REQUIRED

MONITOR SUPPLIED BY (5.4.7.5) Rolls-Royce

LOCATION TCP ENCLOSURE _____

MFR RR Controls MODEL _____

SCALE RGE _____ ALARM SET @ 120 °C

SHTDOWN SET @ 130 °C TIME DLY _____ SEC

REMARKS: _____

NOTES (1) FOR MULTIPLE SHAFT TURBINES, COMPLETE ALL APPLICABLE PORTIONS FOR EACH SHAFT
(2) FOR THREE BEARING SHAFTS, USE A SEPARATE SHEET FOR THE EXTRA BEARING
(3) FOR ROLLING ELEMENT BEARINGS, MODIFY ENTRIES AS REQUIRED. SHOW L-10 BEARING LIFE



ENGINEERS INDIA LIMITED
NEW DELHI

R
E
V

COMBUSTION GAS TURBINE (API 616-4TH)
DATA SHEET
SI UNITS

SPEC NO. 6988-000-KA-MR-501(ITEM NO. _____)

REVISION NO. 0 DATE 5-Apr-09

PAGE 5 OF 10 BY Leong, HT

UTILITIES: CONNECTIONS

UTILITY CONDITIONS: N/A N/A

STEAM: **AUXILIARY DRIVERS** **HEATING**

INLET MIN _____ kPag _____ °C _____ kPag _____ °C

NORM _____ kPag _____ °C _____ kPag _____ °C

MAX _____ kPag _____ °C _____ kPag _____ °C

EXHST MIN. _____ kPag _____ °C _____ kPag _____ °C

NORM _____ kPag _____ °C _____ kPag _____ °C

MAX _____ kPag _____ °C _____ kPag _____ °C

STARTING **N/A** **INJECTION** **N/A**

INLET MIN _____ kPag _____ °C _____ kPag _____ °C

NORM _____ kPag _____ °C _____ kPag _____ °C

MAX _____ kPag _____ °C _____ kPag _____ °C

EXHST MIN. _____ kPag _____ °C

NORM _____ kPag _____ °C

MAX _____ kPag _____ °C

TOTAL UTILITY CONSUMPTION:

COOLING WATER _____ m³/HR

STEAM LEVEL N/A kPag _____ kPag _____ kPag

STEAM, NORMAL N/A _____ kg/HR

STEAM, MAX N/A _____ kg/HR

INSTRUMENT AIR See Utility List in Proposal Nm³/HR

MOTORS (AUXILIARIES) See Utility List in Proposal kW

BATTERY CHARGERS See Utility List in Proposal kW

HEATERS See Utility List in Proposal kW

PURGE (AIR OR N₂) See Utility List in Proposal Nm³/HR

TURBINE AIR EXTRACTION REQUIRED: (4.1.22)

Nm³/HR _____ @ _____ kPag

MAXIMUM PRESSURE AVAILABLE _____ kPag

MINIMUM SPEED _____ RPM

DISCHARGE TEMPERATURE _____ °C

COMPRESSOR EXTRACTION STAGE NUMBER _____

ELECTRICITY: (5.4.6.1) PILOT LIGHT INDICATORS

| | MOTORS | HEATING | CONTROL | SHUTDOWN |
|---------|--------|---------|---------|----------|
| VOLTAGE | 400 | 230 | 230 | 230 |
| HERTZ | 50 | 50 | 50 | 50 |
| PHASE | 3 | 1 | 1 | 1 |

COOLING WATER:

INLET TEMP. _____ °C MAX RETURN _____ °C

DESIGN TEMPERATURE _____ °C

NORM PRESS _____ kPag MIN RETURN _____ kPag

DESIGN PRESS _____ kPag MAX ALLOW D P _____ kPaD

WATER SOURCE _____

INSTRUMENT AIR PRESSURE DESIGN, kPag


MAX 1000 NORMAL 790 MIN 650

REMARKS:

FOR FULL DETAILS OF UTILITY REQUIREMENTS OF THIS GAS TURBINE PACKAGE PLEASE REFER TO THE UTILITY SCHEDULE ATTACHED UNDER TECHNICAL PROPOSAL.

PURCHASER CONNECTIONS

| CONNECTION | DESIGN APPROVAL REQ'D (4.10.4.6.4) | SIZE | FACING and RATING | POSITION (4.4.1) | FLANGED OR STUDD (4.4.1) | MATING FLG & GASKET BY VENDOR (4.4.5.4) | GAS VELOCITY m/SEC |
|----------------------|------------------------------------|-------|-------------------|------------------|--------------------------|-----------------------------------------|--------------------|
| INLET | No | | | TOP / SIDE | | | |
| EXHAUST | No | | | TOP | | | |
| GAS FUEL SUPPLY | No | 2" | 600# RF | | Flanged | Yes | |
| STEAM | N/A | | | N/A | | | |
| WATER | N/A | | | N/A | | | |
| GAS FUEL VENT | No | 1" | 150# RF | | Flanged | | |
| AUXILIARY AIR SUPPLY | No | 0.75" | FNPT | | | | |
| | | | | | | | |
| | | | | | | | |

|  ENGINEERS INDIA LIMITED NEW DELHI | | SPEC NO. <u>6988-000-KA-MR-501</u> (ITEM NO. _____) REVISION NO. <u>0</u> DATE <u>5-Apr-09</u> PAGE <u>6</u> OF <u>10</u> BY <u>Leong, HT</u> | | | | | | | | R E V |
|-------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------|-----------|---------------------|-------------|--------------|----------------------------|--------|--------------------------------|-------------|
| | | COMBUSTION GAS TURBINE (API 616-4TH) DATA SHEET SI UNITS | | | | | | | | |
| INSTRUMENTS | | | | | | | | | | |
| 1 2 3 4 5 6 7 8 9 10 | DESCRIPTION | INSTRUMENT TYPE | | INSTRUMENT LOCATION | | | TRANS-MITTERS FURNISHED BY | | CONTROL ROOM RECEIVERS FURN BY | |
| | | INDICATING | RECORDING | LOCAL | LOCAL PANEL | CONTROL ROOM | VENDOR | OTHERS | VENDOR | OTHERS |
| 11 | GAS GENERATOR OR SINGLE SHAFT GAS TURBINE | | | | | | | | | |
| 12 | TACHOMETER(S) (NO. <u>2</u>) | ● | ● | ○ | ○ | ● | ● | ○ | ● | ○ |
| 13 | Δ P AIR INLET SYSTEM | ● | ○ | ● | ○ | ● | ● | ○ | ● | ○ |
| 14 | COMPRESSOR DISCHARGE PRESSURE | ● | ○ | ○ | ● | ● | ○ | ○ | ● | ○ |
| 15 | FUEL FILTER Δ P | ○ | ○ | ○ | ○ | ○ | ○ | ○ | ○ | ○ |
| 16 | FUEL SUPPLY PRESSURE | ● | ○ | ○ | ○ | ● | ● | ○ | ● | ○ |
| 17 | STARTING GAS SUPPLY PRESSURE | ● | ○ | ○ | ● | ○ | ○ | ○ | ○ | ○ |
| 18 | STARTING GAS EXHAUST PRESSURE | ○ | ○ | ○ | ○ | ○ | ○ | ○ | ○ | ○ |
| 19 | TEMP COMBUSTOR MEASUREMENT (6 PTS MIN) 4.3.2) | ● | ● | ○ | ○ | ● | ● | ○ | ● | ○ |
| 20 | TEMP GAS TURB CONTROL PLANE (6 PTS MIN) | ○ | ○ | ○ | ○ | ○ | ○ | ○ | ○ | ○ |
| 21 | INLET AIR TEMPERATURE | ● | ● | ● | ○ | ● | ● | ○ | ● | ○ |
| 22 | TEMPERATURE GG COMPRESSOR DISCHARGE | ● | ● | ○ | ○ | ● | ● | ○ | ● | ○ |
| 23 | TEMPERATURE THRUST BEARING OIL DRAIN | ○ | ○ | ○ | ○ | ○ | ○ | ○ | ○ | ○ |
| 24 | TEMPERATURE EACH BEARING SUMP (ROLLING ELEMENT TYPE) | ○ | ○ | ○ | ○ | ○ | ○ | ○ | ○ | ○ |
| 25 | TEMPERATURE FUEL MANIFOLD GAS SUPPLY | ● | ○ | ○ | ○ | ● | ● | ○ | ● | ○ |
| 26 | TEMPERATURE LUBE OIL RESERVOIR | ● | ○ | ○ | ○ | ● | ● | ○ | ● | ○ |
| 27 | FIRED HOUR METER | ● | ● | ○ | ○ | ● | ● | ○ | ● | ○ |
| 28 | A) NUMBER STARTS COUNTER | ● | ○ | ○ | ○ | ● | ● | ○ | ● | ○ |
| 29 | B) START SEQUENCE TIMER | ● | ○ | ○ | ○ | ● | ● | ○ | ● | ○ |
| 30 | LUBE OIL RESERVOIR LEVEL | ● | ○ | ● | ○ | ● | ● | ○ | ● | ○ |
| 31 | LUBE OIL PUMP PRESSURE INDICATORS (NO <u>2</u>) | ● | ○ | ○ | ● | ○ | ○ | ○ | ○ | ○ |
| 32 | LUBE OIL COOLER OIL INLET TEMPERATURE | ○ | ○ | ○ | ○ | ○ | ○ | ○ | ○ | ○ |
| 33 | LUBE OIL COOLER OIL OUTLET TEMPERATURE | ● | ○ | ○ | ○ | ● | ● | ○ | ● | ○ |
| 34 | LUBE OIL COOLER COOLANT INLET TEMPERATURE | ○ | ○ | ○ | ○ | ○ | ○ | ○ | ○ | ○ |
| 35 | LUBE OIL COOLER COOLANT OUTLET TEMPERATURE | ○ | ○ | ○ | ○ | ○ | ○ | ○ | ○ | ○ |
| 36 | LUBE OIL FILTER Δ P | ● | ○ | ○ | ● | ○ | ● | ○ | ● | ○ |
| 37 | LUBE OIL PRESSURE EACH LEVEL (NO. <u>1</u>) | ● | ○ | ○ | ● | ● | ● | ○ | ● | ○ |
| 38 | CONTROL OIL PRESSURE | ● | ○ | ○ | ● | ● | ● | ○ | ● | ○ |
| 39 | SITE FLOW INDICATOR EACH DRAIN (NO. <u>N/A</u>) | ○ | ○ | ○ | ○ | ○ | ○ | ○ | ○ | ○ |
| 40 | INLET GUIDE VANE POSITION INDICATOR | ● | ○ | ○ | ○ | ● | ● | ○ | ● | ○ |
| 41 | EXHAUST DUCT Δ P INDICATOR | ○ | ○ | ○ | ○ | ○ | ○ | ○ | ○ | ○ |
| 42 | ENCLOSURE COOLING AIR EXHAUST TEMPERATURE | ● | ○ | ○ | ○ | ● | ● | ○ | ● | ○ |
| 43 | POWER TURBINE | | | | | | | | | |
| 44 | TACHOMETER(S) (NO. <u>1</u>) | ● | ○ | ○ | ○ | ● | ● | ○ | ● | ○ |
| 45 | EXHAUST TEMPERATURE (2 PTS MIN) | ○ | ○ | ○ | ○ | ○ | ○ | ○ | ○ | ○ |
| 46 | JOURNAL BEARING TEMPERATURE | ● | ○ | ○ | ○ | ● | ● | ○ | ● | ○ |
| 47 | THRUST BEARING TEMPERATURE | ● | ○ | ○ | ○ | ● | ● | ○ | ● | ○ |
| 48 | BEARING DRAIN TEMPERATURE | ○ | ○ | ○ | ○ | ○ | ○ | ○ | ○ | ○ |
| 49 | SITE FLOW INDICATOR EACH DRAIN (NO. <u>1 COMMON</u>) | ● | ○ | ● | ○ | ○ | ○ | ○ | ○ | ○ |
| 50 | LUBE OIL INLET PRESSURE | ● | ○ | ○ | ● | ● | ○ | ○ | ● | ○ |
| 51 | LUBE OIL INLET TEMPERATURE | ○ | ○ | ○ | ○ | ○ | ○ | ○ | ○ | ○ |



ENGINEERS INDIA LIMITED
NEW DELHI

COMBUSTION GAS TURBINE (API 616-4TH)
DATA SHEET
SI UNITS

SPEC NO. 6988-000-KA-MR-501(ITEM NO.

REVISION NO. 0 DATE 5-Apr-09

PAGE 7 OF 10 BY Leong, HT

R
E
V

| ALARMS AND SHUTDOWNS (5.4.4) | | | | | | | |
|---------------------------------------------------|----------------------------------|----------------------------------|--------------------------------------------------------------------------|----------------------------------|---------------------------------------------|----------------------------------|--------------------------|
| DESCRIPTION | APPLIES TO: | | (5.4.4.8.5) ANNUNCIATOR POINT IN VENDOR FURNISHED CONTROL PANEL | | SENSING DEVICES TO BE FURNISHED BY | | INDICATING LIGHT ONLY |
| | SINGLE SHAFT OR G.G. | SEP PWR TURB. | (1) | | VENDOR | OTHERS | |
| | | | ALARM | SHUT- DOWN | | | |
| | | | | | | | (2) |
| 9 RADIAL SHAFT VIBRATION (NO. 4) | <input type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 10 AXIAL THRUST POSITION (NO. 2) | <input type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 11 OVERSPEED (1) (NO. 3) | <input type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 12 CASING VIBRATION (NO. 3) | <input checked="" type="radio"/> | <input type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 13 HIGH THRUST BEARING TEMP | <input type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 14 HIGH RADIAL BEARING TEMP | <input type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 15 LOW FUEL SUPPLY PRESSURE | <input checked="" type="radio"/> | <input type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 16 HIGH FUEL FILTER Δ P | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 17 GAS TURBINE TEMPERATURE SPREAD HIGH | <input checked="" type="radio"/> | <input type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 18 EXHAUST OVER TEMP | <input checked="" type="radio"/> | <input type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 19 FAILURE OF OVER-TEMP SHUTDOWN DEVICE | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 20 HIGH INLET AIR Δ P EACH FILTER | <input checked="" type="radio"/> | <input type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 21 COMBUSTOR FLAME-OUT (GG UNDERSPEED) | <input checked="" type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 22 CHIP DETECTOR, ANTI FRICTION BEARING | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 23 FAILURE STARTING CLUTCH TO ENGAGE OR DISENGAGE | <input checked="" type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 24 LOW OIL PRESSURE (NO. 2) | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 25 HIGH LUBE OIL TEMP | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 26 LOW LUBE OIL RESERVOIR LEVEL | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 27 HIGH LUBE OIL RESERVOIR LEVEL | <input checked="" type="radio"/> | <input type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 28 HIGH OIL FILTER Δ P (NO. 2) | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 29 LUBE OIL SPARE PUMP OPERATING | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input checked="" type="radio"/> | <input type="checkbox"/> |
| 30 LOW CONTROL OIL PRESSURE | <input checked="" type="radio"/> | <input type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 31 LOW STARTING GAS PRESSURE | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 32 ANTI-ICING SYSTEM - NOT OPERATING | | | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 33 LOW D.C. VOLTAGE | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 34 EMERGENCY D.C. PUMP OPERATING | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 35 RESERVOIR HEATER "ON" | | | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 36 IMPLOSION DOOR OPEN | | | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 37 EXTERNAL PERMISSIVE START SIGNAL | <input checked="" type="radio"/> | | <input checked="" type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input checked="" type="radio"/> | <input type="checkbox"/> |
| 38 EXTERNAL SHUTDOWN SIGNAL | <input checked="" type="radio"/> | | <input type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input checked="" type="radio"/> | <input type="checkbox"/> |
| 39 LOSS OF AUX COOLING AIR | <input type="radio"/> | | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 40 LAMP TEST PUSH BUTTON | <input type="radio"/> | | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 41 ENCLOSURE HIGH TEMPERATURE | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 42 CONTROL SIGNAL FAILURE | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 43 CONTROL SYSTEM ACTUATOR FAILURE | <input checked="" type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 44 GOVERNOR FAILURE | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 45 ENCLOSURE VENT FAN FAILURE | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input checked="" type="radio"/> | <input checked="" type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 46 | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="radio"/> | <input type="checkbox"/> |
| 47 | | | | | | | |
| 48 | | | | | | | |

NOTES: (1) VENDOR TO ADVISE METHOD OF ANNUNCIATION

(2) VDU MAY USE MESSAGE INDICATOR



ENGINEERS INDIA LIMITED
NEW DELHI

COMBUSTION GAS TURBINE (API 616-4TH)
DATA SHEET
SI UNITS

SPEC NO. 6988-000-KA-MR-501 (ITEM NO. _____)

REVISION NO. 0 DATE 5-Apr-09

PAGE 8 OF 10 BY Leong, HT

R
E
V

ACCESSORIES SUPPLIED BY GAS TURBINE MANUFACTURER

STARTING AND HELPER DRIVERS 5.1)

- STARTER ONLY (5.1.1.2) STARTER/HELPER (5.1.1.3)
- TYPE (5.1.1.1) MOTOR STEAM TURBINE
- GAS EXPANDER IC ENGINE HYDRAULIC
- GAS TURBINE STARTER IS CLUTCHED (5.1.1.7)
- HELPER RATING (5.1.2.2) _____ kW
- STARTER RATING (5.1.2.1) _____ kW
- SHAFT TURNING DEVICE REQUIRED (5.1.3.1)

MOTOR

TYPE _____ RATING 185 kW

MFR _____ MODEL _____

STEAM TURBINE (REFERENCE API DATA SHEETS)

MFR _____ MODEL _____

kW _____ MAX. STEAM FLOW _____ kg/HR

TOTAL/START _____ kg

GAS EXPANDER

APPLICABLE SPEC. (5.1.1.6)

MFR _____ MODEL _____

kW _____ MAX. GAS FLOW _____ kg/HR

TOTAL/START _____ kg

GAS FOR EXPANSION TURBINE:

| | MIN | MAX | NORMAL |
|-----------------------|-------|-------|--------|
| INLET PRESSURE, (kPa) | _____ | _____ | _____ |
| EXHAUST PRESS, (kPa) | _____ | _____ | _____ |
| GAS TEMP., °C INLET | _____ | _____ | _____ |
| GAS TEMP., °C EXHAUST | _____ | _____ | _____ |
| MOLECULAR WEIGHT | _____ | _____ | _____ |

SPEED CONTROL GOVERNOR PRESSURE REGULATOR

YES NO

INLET CONTROL VALVE FURNISHED _____

STAINLESS STEEL PIPING MANIFOLD _____

CARBON STEEL FLANGES _____

Y-STRAINER W/BREAKOUT FLANGES _____

LOW SPEED CAPABILITY _____

(FOR COMPRESSOR CLEANING)

RELIEF VALVE PRESSURE SET POINT _____ kPag

CASING MATERIAL _____

SEAL TYPE _____

INTERNAL COMBUSTION ENGINE

TYPE SPARK IGNITED DIESEL

APPLICABLE SPECIFICATION (5.1.1.6)

MFR _____ MODEL _____

SPEED _____ RPM POWER _____ kW

COMBUSTION GAS TURBINE

APPLICABLE SPEC (5.1.1.6)

MFR _____ MODEL _____

SPEED _____ RPM POWER _____ kW

- GEARS: SEE SEPARATE API 613 GEAR DATA SHEETS (5.2.1.1)
- DRIVEN EQUIPMENT., SEE SEPARATE DATA SHEETS
- FIRE PROTECTION EQUIPMENT (5.7.3.1)
- TYPE HALON 1301 WATER MIST CO₂
- TYPE OF SENSOR NUMBER OF DETECTORS
- HEAT NUMBER 2
- INFRARED NUMBER 3
- INFRARED GAS DETECTORS NUMBER 8

MOUNTING PLATES (5.3)

TYPE (5.3.1.1) SOLEPLATE BASEPLATE

SHIM PACK THICKNESS _____ mm (5.3.1.2.9)

BASEPLATE (5.3.2)

- FURNISHED BY **Rolls-Royce** (5.3.2.1)
- GAS TURBINE ONLY EXTENDED FOR _____
- SUB-SOLEPLATES REQ'D (5.3.2.7) DRIP RIM
- COLUMN MOUNTING (5.3.2.4)(3-POINT) LEVELING PADS (3.3.2.2)

ENCLOSURES (5.7.5)

- ENCLOSURE REQUIRED
- REQUIREMENTS (5.7.5.1)
 - ACOUSTICAL
 - WEATHERPROOF
 - SAFETY
 - FIREPROTECTION
 - POSITIVE VENTILATION (2 X 100%)

COUPLINGS AND GUARDS (5.2.2)

- SEE ATTACHED API-671 DATA SHEETS
- MANUFACTURER _____ TYPE **Dry Flexible**
- MODEL _____ GUARD SUPPLIED BY _____
- MAXIMUM OUTSIDE DIAMETER _____ mm
- HUB WEIGHT _____ kg
- SPACER LENGTH _____ mm SPACER WEIGHT _____ kg
- IDLING ADAPTER REQ'D SOLO PLATE REQ'D
- GUARD SUPPLIED BY **Rolls-Royce**
- TYPE: FULLY ENCLOSED SEMI-OPEN OTHER _____
- LUBRICATING REQUIREMENTS:
 - NON-LUBE GREASE CONT. OIL LUBE
- QUANTITY PER HUB _____ kg or m³/HR

REMARKS: _____



ENGINEERS INDIA LIMITED
NEW DELHI

COMBUSTION GAS TURBINE (API 616-4TH)
DATA SHEET
SI UNITS

SPEC NO. 6988-000-KA-MR-501 (ITEM NO. _____)

REVISION NO. 0 DATE 5-Apr-09

PAGE 9 OF 10 BY Leong, HT

R
E
V

ACCESSORIES SUPPLIED BY GAS TURBINE MANUFACTURER

INLET SYSTEM

EXHAUST SYSTEM

- 3 AIR FILTER (5.5.4.1) **UPDRAFT STATIC FILTER W/ PREFILTER WRAPS**
- 4 INERTIAL TYPE SEPARATOR MEDIA FILTERS
- 5 PREFILTER WRAP COMBINATION
- 6 SELF CLEANING (PULSE TYPE)
- 7 SINGLE STAGE WITH PROVISION FOR
- 8 FUTURE EXTRA STAGES YES NO
- 9 NORMAL DUST LOADING _____ kg/Nm³/HR
- 10 WIND DESIGN VELOCITY 44 m/sec
- 11 SNOW LOAD _____ kg/m²
- 12 SEISMIC ZONE **NON-SEISMIC**
- 13 LOCATION: GROUND LEVEL ELEVATED (5.5.4.6)
- 14 FILTRATION EFFICIENCY _____ % (5.5.4.3)
- 15 MAINTENANCE INTERVAL _____ MONTHS
- 16 CLEANING FREQUENCY _____ DAYS
- 17 IMPLOSION DOOR (5.5.4.5)
- 18 EVAPORATIVE COOLER (5.6.1.1) ANTI-ICING (5.5.3.10)
- 19 LIQUID TO AIR EXCHANGER (5.6.2.2)
- 20 WALKWAYS, LADDERS, HANDRAILS REQUIRED (5.6.1.5)
- 21 COMP CLEANING SYSTEM, TYPE Crank Soak Wash (5.5.3.9)
- 22 SILENCER PLATE ELEMENT MAT'L (5.5.5.1.4) 304 SST
- 23 FILTER MFR. _____ MODEL _____
- 24 @ 110% RATED AIR FLOW ΔP _____ mm H₂O
- 25 CLEAN _____ mm H₂O ALARM _____ mm H₂O
- 26 COOLER MFR. _____ MODEL _____ ΔP _____ mm H₂O
- 27 EXCHANGER MFR (5.6.2.3) _____
- 28 MODEL _____ ΔP _____ mm H₂O
- 29 DUCTING GAUGE / MATERIAL _____ / See remark-1
- 30 EXPANSION JOINT MFR _____ TYPE _____
- 31 SILENCER MFR _____ ΔP _____ mm H₂O
- 32 MANOMETER MFR _____ MODEL _____
- 33 RANGE _____ mm H₂O
- 34 SYSTEM SITE RATED PRESSURE DROP 100 mm H₂O
- 35 @ 110% RATED AIR FLOW

- EXTENT OF FURN. INSULATION (SEE SKETCH) (5.7.1.2)
- (RELIEF) (DIVERSION) VALVE (5.5.6.8)
- EXHAUST HEAT RECOVERY SYSTEM (5.5.3.1)
- EMISSION CONTROL SYSTEM (5.5.3.1)
- EXHAUST SILENCER PLATE ELEMENT MATERIAL (5.5.5.2.3) _____
- CARBON STEEL W/ 409 SST FLOW LINER**
- EMISSIONS SAMPLING SYSTEM (5.5.6.10)
- EXPANSION JOINT MFR _____ TYPE _____
- DUCTING GAUGE/MATERIAL _____ / _____
- SILENCER MFR _____ ΔP _____ mm H₂O
- HEAT RECOVERY DEVICE
- MFR _____ TYPE _____ ΔP _____ mm H₂O
- STEAM GEN: PRESS _____ kPag TEMP _____ °C
- RATE _____ kg/HR
- MANOMTR MFR _____ MODEL _____ RANGE _____ mm H₂O
- ATMOSPHERIC RELIEF DEVICE (5.5.6.8)
- TYPE _____ MFR _____ LOCATION _____
- SYSTEM SITE RATED PRESSURE DROP 250 mm H₂O


ATMOSPHERIC EMISSIONS

- EMISSION SUPPRESSION SYSTEM REQUIRED (5.8.4.1)
- NO_x REQUIREMENTS (5.5.3.1.1) 100PPMV @15% O2
- NO_x EMITTED _____
- EMISSIONS REDUCTION METHOD (IF REQUIRED) (5.8.4.2)**
- WATER INJECTION (5.8.4.4) SCR
- STEAM (5.8.4.4) DRY COMBUSTOR
- OTHER _____
- SO_x REQUIREMENTS _____
- SULFUR CONTENT OF FUEL _____
- SO_x EMITTED (BASED ON STATED SULFUR CONTENT) _____
- CO REQUIREMENTS _____
- CO EMITTED _____
- PARTICULATE REQUIREMENTS _____
- PARTICULATE EMITTED _____
- UNBURNED HC REQUIREMENTS _____
- UNBURNED HC EMITTED _____
- APPLICABLE EMISSION CODES OR REGULATIONS**
- EPA - TITLE 40 - CFR OTHERS _____

SPECIALIZED INSTRUMENTS

- 45 **TACHOMETERS (5.4.7.2.2)**
- 46 TYPE ELECTRICAL ELECTRONIC
- 47 ANALOG DIGITAL
- 48 MANUFACTURER Rolls-Royce Controls
- 49 OIL FILLED PRESSURE GAUGES (5.4.7.6)

- SWITCHES: (5.4.4.8.2)
- CIRCUIT SHALL
- ENERGIZE DEENERGIZE TO ALARM
- ENERGIZE DEENERGIZE TO SHUTDOWN
- ENCLOSURES
- EXPLOSION PROOF WEATHER PROOF

|  ENGINEERS INDIA LIMITED NEW DELHI | SPEC NO. <u>6988-000-KA-MR-501</u> (ITEM NO. _____) REVISION NO. <u>0</u> DATE <u>5-Apr-09</u> PAGE <u>10</u> OF <u>10</u> BY <u>Leong, HT</u> | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------|--------------------|------------------|-----|---|-------------------------------------------|--|--|--|---|--|--|--|--|---|-------------------------|---|--|--|---|-----------------------|---|--|--|---|---------------------|---|---|---|---|------------------------|---|---|---|---|--------------------------------------------|--|--|--|---|--------------------------------------------|--|--|--|----|-----------------------------------------------------|--|--|--|----|--------------------------------------|--|--|--|----|-----------------------------|---|--|--|----|--------------------------------|---|--|--|----|-------------------------------------|---|---|---|----|---------------------------------------|---|---|---|----|--------------------------|---|---|---|----|--------------------------|---|---|---|----|---------------------------------------------|---|---|---|----|-------------------------------|---|---|---|----|--------------------------------|---|---|---|----|---------|---|---|---|----|----------------------------------|---|---|---|----|-----------------------|---|---|---|----|---------------------------------------|---|---|---|----|------------------------|---|---|---|----|--|--|--|--|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|----------------------------|------------------|--------------------|------------------------------------------------------|--|--|--|----|--|--|--|---------------|--|--|--|------|--|--|--|-----------|--|--|--|---------------|--|--|--|--------------|--|--|--|--|-----------------------|----------------------|--------------------|------------------|--|--|--|----------------|--|--|--|---------------|--|--|--|------------|--|--|--|-------------|--|--|--|---------------|--|--|--|--------|--|--|--|----------------|--|--|--|------------------|--|--|--|---------|--|--|--|--------------------------|--|------|--|------------------------|--|------|--|
| COMBUSTION GAS TURBINE (API 616-4TH) DATA SHEET SI UNITS | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| INSPECTION AND TESTING; LUBRICATION, WEIGHTS | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| <table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:5%; text-align: center;">1</td> <td style="width:35%;"></td> <td style="width:10%; text-align: center;">WIT- REQ</td> <td style="width:10%; text-align: center;">OBSER- NESSED</td> <td style="width:10%; text-align: center;">VED</td> </tr> <tr> <td style="text-align: center;">2</td> <td>SHOP INSPECTION AND TESTS: (6.1.1)</td> <td></td> <td></td> <td></td> </tr> <tr> <td style="text-align: center;">3</td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td style="text-align: center;">4</td> <td>SHOP INSPECTION (6.1.2)</td> <td style="text-align: center;">●</td> <td></td> <td></td> </tr> <tr> <td style="text-align: center;">5</td> <td>CLEANLINESS (6.2.3.3)</td> <td style="text-align: center;">●</td> <td></td> <td></td> </tr> <tr> <td style="text-align: center;">6</td> <td>HYDROSTATIC (6.3.2)</td> <td style="text-align: center;">●</td> <td style="text-align: center;">○</td> <td style="text-align: center;">○</td> </tr> <tr> <td style="text-align: center;">7</td> <td>MECHANICAL RUN (6.3.3)</td> <td style="text-align: center;">●</td> <td style="text-align: center;">●</td> <td style="text-align: center;">○</td> </tr> <tr> <td style="text-align: center;">8</td> <td><input type="checkbox"/> CONTRACT COUPLING</td> <td></td> <td></td> <td></td> </tr> <tr> <td style="text-align: center;">9</td> <td><input type="checkbox"/> IDLING ADAPTOR(S)</td> <td></td> <td></td> <td></td> </tr> <tr> <td style="text-align: center;">10</td> <td><input checked="" type="checkbox"/> CONTRACT PROBES</td> <td></td> <td></td> <td></td> </tr> <tr> <td style="text-align: center;">11</td> <td><input type="checkbox"/> SHOP PROBES</td> <td></td> <td></td> <td></td> </tr> <tr> <td style="text-align: center;">12</td> <td>VIBRATION PLOTS (6.3.3.3.4)</td> <td style="text-align: center;">●</td> <td></td> <td></td> </tr> <tr> <td style="text-align: center;">13</td> <td>TAPE RECORD VIB DATA (6.3.3.6)</td> <td style="text-align: center;">○</td> <td></td> <td></td> </tr> <tr> <td style="text-align: center;">14</td> <td>PERFORMANCE TEST (6.3.4.1) (PTC-22)</td> <td style="text-align: center;">●</td> <td style="text-align: center;">●</td> <td style="text-align: center;">○</td> </tr> <tr> <td style="text-align: center;">15</td> <td>NO LOAD STRING TEST (ONE PER STATION)</td> <td style="text-align: center;">●</td> <td style="text-align: center;">●</td> <td style="text-align: center;">○</td> </tr> <tr> <td style="text-align: center;">16</td> <td>PACKAGE TEST (6.3.4.2.1)</td> <td style="text-align: center;">○</td> <td style="text-align: center;">○</td> <td style="text-align: center;">○</td> </tr> <tr> <td style="text-align: center;">17</td> <td>LOAD GEAR TEST (6.3.4.3)</td> <td style="text-align: center;">○</td> <td style="text-align: center;">○</td> <td style="text-align: center;">○</td> </tr> <tr> <td style="text-align: center;">18</td> <td>NOISE SURVEY (6.3.4.4) (DURING STRING TEST)</td> <td style="text-align: center;">●</td> <td style="text-align: center;">●</td> <td style="text-align: center;">○</td> </tr> <tr> <td style="text-align: center;">19</td> <td>AUXILIARY EQUIPMENT (6.3.4.5)</td> <td style="text-align: center;">●</td> <td style="text-align: center;">○</td> <td style="text-align: center;">○</td> </tr> <tr> <td style="text-align: center;">20</td> <td>POST TEST INSPECTION (6.3.4.6)</td> <td style="text-align: center;">○</td> <td style="text-align: center;">○</td> <td style="text-align: center;">○</td> </tr> <tr> <td style="text-align: center;">21</td> <td>UCP FAT</td> <td style="text-align: center;">●</td> <td style="text-align: center;">○</td> <td style="text-align: center;">○</td> </tr> <tr> <td style="text-align: center;">22</td> <td>GOVERNOR RESPONSE TEST (6.3.4.8)</td> <td style="text-align: center;">○</td> <td style="text-align: center;">○</td> <td style="text-align: center;">○</td> </tr> <tr> <td style="text-align: center;">23</td> <td>SPARE PARTS (6.3.4.9)</td> <td style="text-align: center;">○</td> <td style="text-align: center;">○</td> <td style="text-align: center;">○</td> </tr> <tr> <td style="text-align: center;">24</td> <td>FIRE PROTECTION SIMULATION (6.3.4.10)</td> <td style="text-align: center;">○</td> <td style="text-align: center;">○</td> <td style="text-align: center;">○</td> </tr> <tr> <td style="text-align: center;">25</td> <td>OTHER (6.3.4.11) _____</td> <td style="text-align: center;">○</td> <td style="text-align: center;">○</td> <td style="text-align: center;">○</td> </tr> <tr> <td style="text-align: center;">26</td> <td></td> <td></td> <td></td> <td></td> </tr> </table> | 1 | | WIT- REQ | OBSER- NESSED | VED | 2 | SHOP INSPECTION AND TESTS: (6.1.1) | | | | 3 | | | | | 4 | SHOP INSPECTION (6.1.2) | ● | | | 5 | CLEANLINESS (6.2.3.3) | ● | | | 6 | HYDROSTATIC (6.3.2) | ● | ○ | ○ | 7 | MECHANICAL RUN (6.3.3) | ● | ● | ○ | 8 | <input type="checkbox"/> CONTRACT COUPLING | | | | 9 | <input type="checkbox"/> IDLING ADAPTOR(S) | | | | 10 | <input checked="" type="checkbox"/> CONTRACT PROBES | | | | 11 | <input type="checkbox"/> SHOP PROBES | | | | 12 | VIBRATION PLOTS (6.3.3.3.4) | ● | | | 13 | TAPE RECORD VIB DATA (6.3.3.6) | ○ | | | 14 | PERFORMANCE TEST (6.3.4.1) (PTC-22) | ● | ● | ○ | 15 | NO LOAD STRING TEST (ONE PER STATION) | ● | ● | ○ | 16 | PACKAGE TEST (6.3.4.2.1) | ○ | ○ | ○ | 17 | LOAD GEAR TEST (6.3.4.3) | ○ | ○ | ○ | 18 | NOISE SURVEY (6.3.4.4) (DURING STRING TEST) | ● | ● | ○ | 19 | AUXILIARY EQUIPMENT (6.3.4.5) | ● | ○ | ○ | 20 | POST TEST INSPECTION (6.3.4.6) | ○ | ○ | ○ | 21 | UCP FAT | ● | ○ | ○ | 22 | GOVERNOR RESPONSE TEST (6.3.4.8) | ○ | ○ | ○ | 23 | SPARE PARTS (6.3.4.9) | ○ | ○ | ○ | 24 | FIRE PROTECTION SIMULATION (6.3.4.10) | ○ | ○ | ○ | 25 | OTHER (6.3.4.11) _____ | ○ | ○ | ○ | 26 | | | | | <p>LUBRICATION SYSTEMS (4.9)</p> <p>● SEE API 614 DATA SHEETS MINERAL OIL SYSTEM</p> <p><input type="checkbox"/> LUBE OIL VISCOSITY (4.9.8) ISO GRADE ISO VG 32 / 46</p> <p>COMMON TO <input type="checkbox"/> GAS GENERATOR/SINGLE SHAFT TURBINE</p> <p><input checked="" type="checkbox"/> FREE POWER TURBINE <input checked="" type="checkbox"/> LOAD GEAR (IF APPLICABLE)</p> <p><input checked="" type="checkbox"/> DRIVEN EQUIPMENT <input type="checkbox"/> AUXILIARIES</p> <p><input type="checkbox"/> (COMBINED) (SEPARATE) LUBE/SEAL SYSTEM (4.9.5)</p> <p>● SYSTEM DESIGNED FOR SYNTHETIC LUBRICANT (4.9.2)</p> <p>LUBE SPECIFICATION Rolls-Royce Approved Synthetic Oil</p> <p>COMMON TO <input checked="" type="checkbox"/> GAS GENERATOR <input type="checkbox"/> POWER TURBINE</p> <p><input type="checkbox"/> LOAD GEAR <input type="checkbox"/> DRIVEN EQUIPMENT</p> <p><input type="checkbox"/> AUXILIARIES</p> <table border="1" style="width:100%; border-collapse: collapse; margin-top: 10px;"> <thead> <tr> <th style="width:60%;"></th> <th style="width:10%;">FLOW m³/HR</th> <th style="width:10%;">PRESSURE kPag</th> <th style="width:10%;">HEAT LOAD MJ/HR</th> </tr> </thead> <tbody> <tr> <td><input checked="" type="checkbox"/> OIL REQUIREMENTS</td> <td></td> <td></td> <td></td> </tr> <tr> <td>GG</td> <td></td> <td></td> <td></td> </tr> <tr> <td>DRIVEN EQUIP.</td> <td></td> <td></td> <td></td> </tr> <tr> <td>GEAR</td> <td></td> <td></td> <td></td> </tr> <tr> <td>COUPLINGS</td> <td></td> <td></td> <td></td> </tr> <tr> <td>POWER TURBINE</td> <td></td> <td></td> <td></td> </tr> <tr> <td style="text-align: right;">TOTAL</td> <td></td> <td></td> <td></td> </tr> </tbody> </table> <p>MOUNTING ARRANGEMENT</p> <p><input type="checkbox"/> CONSOLE <input type="checkbox"/> COLONY <input type="checkbox"/> BASEPLATE</p> <p>WEIGHTS</p> <table border="1" style="width:100%; border-collapse: collapse; margin-top: 10px;"> <thead> <tr> <th style="width:60%;"></th> <th style="width:10%;">INSTALLED WT. (kg)</th> <th style="width:10%;">SHIPPING WT. (kg)</th> <th style="width:10%;">DIMEN LxWxH (m)</th> </tr> </thead> <tbody> <tr> <td>GG OR SS TURBINE</td> <td></td> <td></td> <td></td> </tr> <tr> <td>SS TURB. ROTOR</td> <td></td> <td></td> <td></td> </tr> <tr> <td>POWER TURBINE</td> <td></td> <td></td> <td></td> </tr> <tr> <td>P.T. ROTOR</td> <td></td> <td></td> <td></td> </tr> <tr> <td>LUBE SYSTEM</td> <td></td> <td></td> <td></td> </tr> <tr> <td>DRIVEN EQUIP.</td> <td></td> <td></td> <td></td> </tr> <tr> <td>FILTER</td> <td></td> <td></td> <td></td> </tr> <tr> <td>INLET SILENCER</td> <td></td> <td></td> <td></td> </tr> <tr> <td>EXHAUST SILENCER</td> <td></td> <td></td> <td></td> </tr> <tr> <td>DUCTING</td> <td></td> <td></td> <td></td> </tr> <tr> <td>MAX ERECTION WEIGHT (kg)</td> <td></td> <td>ITEM</td> <td></td> </tr> <tr> <td>MAX MAINT. WEIGHT (kg)</td> <td></td> <td>ITEM</td> <td></td> </tr> </tbody> </table> | | FLOW m ³ /HR | PRESSURE kPag | HEAT LOAD MJ/HR | <input checked="" type="checkbox"/> OIL REQUIREMENTS | | | | GG | | | | DRIVEN EQUIP. | | | | GEAR | | | | COUPLINGS | | | | POWER TURBINE | | | | TOTAL | | | | | INSTALLED WT. (kg) | SHIPPING WT. (kg) | DIMEN LxWxH (m) | GG OR SS TURBINE | | | | SS TURB. ROTOR | | | | POWER TURBINE | | | | P.T. ROTOR | | | | LUBE SYSTEM | | | | DRIVEN EQUIP. | | | | FILTER | | | | INLET SILENCER | | | | EXHAUST SILENCER | | | | DUCTING | | | | MAX ERECTION WEIGHT (kg) | | ITEM | | MAX MAINT. WEIGHT (kg) | | ITEM | |
| 1 | | WIT- REQ | OBSER- NESSED | VED | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 2 | SHOP INSPECTION AND TESTS: (6.1.1) | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 3 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 4 | SHOP INSPECTION (6.1.2) | ● | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 5 | CLEANLINESS (6.2.3.3) | ● | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 6 | HYDROSTATIC (6.3.2) | ● | ○ | ○ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 7 | MECHANICAL RUN (6.3.3) | ● | ● | ○ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 8 | <input type="checkbox"/> CONTRACT COUPLING | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 9 | <input type="checkbox"/> IDLING ADAPTOR(S) | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 10 | <input checked="" type="checkbox"/> CONTRACT PROBES | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 11 | <input type="checkbox"/> SHOP PROBES | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 12 | VIBRATION PLOTS (6.3.3.3.4) | ● | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 13 | TAPE RECORD VIB DATA (6.3.3.6) | ○ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 14 | PERFORMANCE TEST (6.3.4.1) (PTC-22) | ● | ● | ○ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 15 | NO LOAD STRING TEST (ONE PER STATION) | ● | ● | ○ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 16 | PACKAGE TEST (6.3.4.2.1) | ○ | ○ | ○ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 17 | LOAD GEAR TEST (6.3.4.3) | ○ | ○ | ○ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 18 | NOISE SURVEY (6.3.4.4) (DURING STRING TEST) | ● | ● | ○ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 19 | AUXILIARY EQUIPMENT (6.3.4.5) | ● | ○ | ○ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 20 | POST TEST INSPECTION (6.3.4.6) | ○ | ○ | ○ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 21 | UCP FAT | ● | ○ | ○ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 22 | GOVERNOR RESPONSE TEST (6.3.4.8) | ○ | ○ | ○ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 23 | SPARE PARTS (6.3.4.9) | ○ | ○ | ○ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 24 | FIRE PROTECTION SIMULATION (6.3.4.10) | ○ | ○ | ○ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 25 | OTHER (6.3.4.11) _____ | ○ | ○ | ○ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 26 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | FLOW m ³ /HR | PRESSURE kPag | HEAT LOAD MJ/HR | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| <input checked="" type="checkbox"/> OIL REQUIREMENTS | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| GG | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| DRIVEN EQUIP. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| GEAR | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| COUPLINGS | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| POWER TURBINE | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| TOTAL | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | INSTALLED WT. (kg) | SHIPPING WT. (kg) | DIMEN LxWxH (m) | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| GG OR SS TURBINE | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| SS TURB. ROTOR | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| POWER TURBINE | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| P.T. ROTOR | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| LUBE SYSTEM | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| DRIVEN EQUIP. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| FILTER | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| INLET SILENCER | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| EXHAUST SILENCER | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| DUCTING | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| MAX ERECTION WEIGHT (kg) | | ITEM | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| MAX MAINT. WEIGHT (kg) | | ITEM | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| <p>MATERIALS INSPECTION REQUIREMENTS (6.2.1.3)</p> <p><input type="checkbox"/> SPECIAL CHARPY TESTING (4.10.5.3) _____</p> <p><input type="checkbox"/> RADIOGRAPHY REQUIRED FOR _____</p> <p><input type="checkbox"/> MAGNETIC PARTICLE REQUIRED FOR _____</p> <p><input type="checkbox"/> LIQUID PENETRANT REQUIRED FOR _____</p> <p><input type="checkbox"/> ULTRASONIC REQUIRED FOR _____</p> <p><input type="checkbox"/> WELD INSPECTION (4.10.4.6.1) _____</p> <p><input type="checkbox"/> WELDING HARDNESS TESTING (6.2.3.4) _____</p> | <p>MISCELLANEOUS:</p> <p><input checked="" type="checkbox"/> VENDOR'S REVIEW & COMMENTS ON PURCHASER'S PIPING & FOUNDATION (4.1.18)</p> <p><input checked="" type="checkbox"/> FINAL ASSEMBLY CLEARANCES (6.2.1.1.e)</p> <p><input checked="" type="checkbox"/> COORDINATION MEETING SITE (7.1.3) <u>Supplier's Facility</u></p> <p><input type="checkbox"/> SPEED-TORQUE CURVE (7.2.4-a)</p> <p><input type="checkbox"/> INCREASE POWER FOR STEAM/WATER (7.2.4-b)</p> <p><input type="checkbox"/> EFFECTS OF AMB. COND. ON EXHAUST FLOW (7.2.4-c)</p> <p><input type="checkbox"/> RUN DOWN CURVES (7.2.4 d)</p> <p><input type="checkbox"/> PURCHASER REVIEW OF CAMP./GOODMAN DIAG. (4.5.3.3)</p> <p><input type="checkbox"/> VENDOR WITNESS ALIGNMENT (4.1.18)</p> <p><input checked="" type="checkbox"/> TECHNICAL DATA MANUAL (7.3.6.4)</p> <p><input type="checkbox"/> NO OF PROPOSAL COPIES (7.2.1) _____</p> | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| <p>REMARKS:</p> <p>_____</p> <p>_____</p> <p>_____</p> | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |



eRB211 v6.1.4

31 March 2009

Customer: GAIL
Project: Pipeline Expansion Project
RB211-GT61
DLE Combustion

Site Conditions - Chainsa

Ambient Temp : 45degC
Altitude : 197.8m
Relative Humidity : 84%


Fuel

Fuel Type: Lean gas
Fuel LHV: 49602 kJ/kg

Installation Pressure Losses

Inlet: 100 mmH2O
Exhaust: 250 mmH2O

Expected Heat Rate kJ/kW.hr



COMPRESSOR STATION WORKS AT KAILARAS & CHAINSA -COMPRESSOR PACKAGE

| | | | |
|-----------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------|----------------------|-----------------------------|
| OPERATING CASE: <u>CHAINSA (Lean Gas, MW=17.07)</u> | | | |
| 1. | <u>Compressor</u> | | |
| 1.1 | BKW required at compressor input shaft including all losses (with 0% positive tolerance) | kW | : 20680 (GUARANTEED) |
| 2. | <u>Gas Turbine Site Rating</u> Ū | | |
| 2.1 | GT Site Rating @ 45EC (at compressor operating point speed) | kW | : 23546 (GUARANTEED) |
| 3. | <u>Heat Rate at Site Conditions</u> (while generating rated BKW as at 1 above) | | |
| | GT Heat rate @ 45EC (at compressor operating point speed) | kJ/kWh kcal/kWh | : 10704 / 2557 (GUARANTEED) |
| 3.1 | Ū These figures correspond to the following site/operating conditions: | | |
| | i) Expected TBO (Hot Section) | hrs | : 25000 |
| | ii) Expected TBO (Power Turbine) | hrs | : 50000 |
| | iii) GG Rated Speed | rpm | : 6395 / 9326 |
| | iv) PT Rated Speed | rpm | : 4850 |
| | v) Gas Turbine ISO Rating (with losses below) | kW | : 31213 |
| | vi) Site Altitude | m | : 197.8 |
| | vii) Max. Inlet Loss (At Site) | mm H ₂ O | : 100 |
| | viii) Max. Exhaust Loss (At site) with Heat recovery in future | mm H ₂ O | : 250 |
| | ix) Site Rated/Temperature | EC | : 45 |
| | x) Relative Humidity | % | : 84 |
| | xi) GGT Inlet Temperature (GG Exit Temp) [While generating site rated power] | EC | : 801.8 |
| | Xii) NHV of fuel gas (LHV) | kcal/Sm ³ | : 8565 |
| 4. | Overall compressor package noise level @ 1 meter from the equipment train (Including compressor, turbine and other aux. equipment & piping). | dBA | : |

(NOTE: - This is a typical data sheet. Bidder shall furnish data sheets filled for each operating case of each compressor station with Proposal).

| | | | | |
|-------------------------------------------------------------------------------------|---------------------------------------------|-------------------------------|----------------------------|-------------|
|  | ENGINEERS INDIA LIMITED NEW DELHI | COMBUSTION GAS TURBINE | DATA SHEET NO. | Rev. |
| | | | 6988-000-KT-DS-0020 | 0 |

COMPRESSOR STATION WORKS AT KAILARAS & CHAINSA -COMPRESSOR PACKAGE

| | | | |
|----------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------|---------------|
| OPERATING CASE: <u>CHAINSA (Rich Gas, MW=17.4)</u> | | | |
| 1. | <u>Compressor</u> | | |
| 1.1 | BKW required at compressor input shaft including all losses (with 0% positive tolerance) | kW | : 20943 |
| 2. | <u>Gas Turbine Site Rating</u> U | | |
| 2.1 | GT Site Rating @ 45EC (at compressor operating speed) | kW | : 23547 |
| 3. | <u>Heat Rate at Site Conditions</u> (while generating rated BKW as at 1 above) | | |
| | GT Heat rate @ 45EC (at compressor operating point speed) | kJ/kWh kcal/kWh : 10176 / 2430 | |
| 3.1 | U These figures correspond to the following site/operating conditions: | | |
| | i) Expected TBO (Hot Section) | hrs | : 25000 |
| | ii) Expected TBO (Power Turbine) | hrs | : 50000 |
| | iii) GG Rated Speed | rpm | : 6396 / 9326 |
| | iv) PT Rated Speed | rpm | : 4837 |
| | v) Gas Turbine ISO Rating (with losses below) | kW | : 31199 |
| | vi) Site Altitude | m | : 197.8 |
| | vii) Max. Inlet Loss (At Site) | mm H ₂ O | : 100 |
| | viii) Max. Exhaust Loss (At site) with Heat recovery in future | mm H ₂ O | : 250 |
| | ix) Site Rated/Temperature | EC | : 45 |
| | x) Relative Humidity | % | : 84 |
| | xi) GGT Inlet Temperature (GG Exit Temp) [While generating site rated power] | EC | : 801.8 |
| | Xii) NHV of fuel gas (LHV) | kcal/Sm ³ | : 8716 |
| 4. | Overall compressor package noise level @ 1 meter from the equipment train (Including compressor, turbine and other aux. equipment & piping). | dBA | : |

(NOTE: - This is a typical data sheet. Bidder shall furnish data sheets filled for each operating case of each compressor station with Proposal).

| | | | | |
|-------------------------------------------------------------------------------------|---------------------------------------------|-------------------------------|-----------------------|-------------|
|  | ENGINEERS INDIA LIMITED NEW DELHI | COMBUSTION GAS TURBINE | DATA SHEET NO. | Rev. |
| | | | 6988-000-KT-DS-0020 | 0 |

COMPRESSOR STATION WORKS AT KAILARAS & CHAINSA (GT –COMPRESSOR PACKAGE)

| PERFORMANCE TABLE | | | | | | | |
|---------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------|-----------------------------------------------|---------------------|---------------|---------------|---------|
| Sr No | DESCRIPTION | UNITS | OPERATING CASE : CHAINSA (Lean Gas, MW=17.07) | | | | Remarks |
| | | | ISO | Rated | Max | Min | |
| | | | 1 | Ambient temperature | °C | 15 | |
| 2 | Relative humidity | % | 60 | 84 | 84 | 37 | |
| 3 | NHV of Fuel gas | kcal/kg | 11847 | 11847 | 11847 | 11847 | |
| 4 | Compressor Power at High speed Coupling (incl. Of mech. Seal losses) | kW | 20680 | 20680 | 20680 | 20680 | |
| 5 | Rated Speed of the Compressor | rpm | 4850 | 4850 | 4850 | 4850 | |
| 6 | Mech. Losses of Gas Turbine (Power to all auxiliaries) | kW | 0 | 0 | 0 | 0 | |
| 7 | Power Turbine Shaft speed | rpm | 4850 | 4850 | 4850 | 4850 | |
| 8 | Power required on Power Turbine Shaft [= (4) + (6)] | kW | 20680 | 20680 | 20680 | 20680 | |
| 9 | Site efficiency | % | 35.31 | 33.63 | 33.63 | 35.75 | |
| 10 | H _R : Heat Rate corresponding to (8) | kJ/kWh kcal/kWh | 10195 2435 | 10704 2557 | 10704 2557 | 10069 2405 | |
| 11 | W _{max} : Max. Power on PT Shaft at corresponding shaft speed Site Elevation = 197.8 m (As per site & Utility Data) Max. Inlet pressure Losses = 100 mm H ₂ O Max. Exhaust Pressure Losses = 250 mm H ₂ O & Including all other losses | kW | 31213 | 23546 | 23546 | 34837 | |
| 12 | η _S corresponding to W _{max} . | % | 38.76 | 35.38 | 35.38 | 39.68 | |
| 13 | H _R corresponding to W _{max} . | kJ/kWh kcal/kWh | 9289 2219 | 10176 2430 | 10176 2430 | 9072 2167 | |
| 14 | T _S : PT Exhaust Temperature | °C | 451.9 | 520.0 | 520.0 | 416.9 | |
| 15 | GG Exhaust Temp | °C | 698.5 | 774.0 | 774.0 | 656.9 | |
| 16 | Firing Temp | °C | Proprietary | Proprietary | Proprietary | Proprietary | |
| 17 | Exhaust Flow | kg/sec | 78.1 | 71.5 | 71.5 | 81.3 | |
| 18 | Actual Margin available with offered GT [= {(11) – (8)}/(8) * 100] | % | 50.93 | 13.86 | 13.86 | 68.46 | |
| (NOTE: - This is a typical data sheet. Bidder shall furnish data sheets filled for each operating case of each compressor station with Proposal). | | | | | | | |

COMPRESSOR STATION WORKS AT KAILARAS & CHAINSA (GT –COMPRESSOR PACKAGE)

| PERFORMANCE TABLE | | | | | | | |
|---------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------|----------------------------------------------|---------------------|---------------|---------------|---------|
| Sr No | DESCRIPTION | UNITS | OPERATING CASE : CHAINSA (Rich Gas, MW=17.4) | | | | Remarks |
| | | | ISO | Rated | Max | Min | |
| | | | 1 | Ambient temperature | °C | 15 | |
| 2 | Relative humidity | % | 60 | 84 | 84 | 37 | |
| 3 | NHV of Fuel gas | kcal/kg | 11824 | 11824 | 11824 | 11824 | |
| 4 | Compressor Power at High speed Coupling (incl. Of mech. Seal losses) | kW | 20943 | 20943 | 20943 | 20943 | |
| 5 | Rated Speed of the Compressor | rpm | 4837 | 4837 | 4837 | 4837 | |
| 6 | Mech. Losses of Gas Turbine (Power to all auxiliaries) | kW | 0 | 0 | 0 | 0 | |
| 7 | Power Turbine Shaft speed | rpm | 4837 | 4837 | 4837 | 4837 | |
| 8 | Power required on Power Turbine Shaft [= (4) + (6)] | kW | 20943 | 20943 | 20943 | 20943 | |
| 9 | Site efficiency | % | 35.45 | 34.26 | 34.26 | 35.90 | |
| 10 | H _R : Heat Rate corresponding to (8) | kJ/kWh kcal/kWh | 10155 2425 | 10507 2510 | 10507 2510 | 10028 2395 | |
| 11 | W _{max} : Max. Power on PT Shaft at corresponding shaft speed Site Elevation = 197.8 m (As per site & Utility Data) Max. Inlet pressure Losses = 100 mm H ₂ O Max. Exhaust Pressure Losses = 250 mm H ₂ O & Including all other losses | kW | 31199 | 23547 | 23547 | 34823 | |
| 12 | η _S corresponding to W _{max} . | % | 38.74 | 35.38 | 35.38 | 39.67 | |
| 13 | H _R corresponding to W _{max} . | kJ/kWh kcal/kWh | 9292 2219 | 10176 2430 | 10176 2430 | 9075 2168 | |
| 14 | T _S : PT Exhaust Temperature | °C | 452.6 | 520.9 | 520.9 | 417.5 | |
| 15 | GG Exhaust Temp | °C | 700.9 | 776.6 | 776.6 | 659.2 | |
| 16 | Firing Temp | °C | Proprietary | Proprietary | Proprietary | Proprietary | |
| 17 | Exhaust Flow | kg/sec | 78.5 | 71.9 | 71.9 | 81.7 | |
| 18 | Actual Margin available with offered GT [= {(11) – (8)}/(8) * 100] | % | 48.97 | 12.43 | 12.43 | 66.28 | |
| (NOTE: - This is a typical data sheet. Bidder shall furnish data sheets filled for each operating case of each compressor station with Proposal). | | | | | | | |